



Addendum No. 1

June 13, 2019

**Project: ANNUAL STREET RESURFACING PROJECT FISCAL YEAR
2018-2019 JOB NO. 7597, PLAN NO. P-726**

A. The following change to the **Bid Schedule** shall apply for this project. See attached sheets P-2 to P-4

1. Previously stated as:

**WATER IMPROVEMENTS
SUBTOTAL ITEMS 15-20**

**SEWER IMPROVEMENTS
SUBTOTALS ITEMS 21-26**

TOTAL BID AMOUNT 1-26

2. Changed to:

**WATER IMPROVEMENTS
SUBTOTAL ITEMS 15-21**

**SEWER IMPROVEMENTS
SUBTOTALS ITEMS 22-27**

TOTAL BID AMOUNT 1-27

Indicate the receipt of Addendum 1 on Page P-2 of the Contractor's Proposal. **FAILURE TO DO SO WILL RENDER YOUR BID NON-RESPONSIVE**

Approved by:

Manuel Fabian
Civil Engineering Assistant II

Date

BID SCHEDULE

ANNUAL STREET RESURFACING PROJECT FISCAL YEAR 2018-2019 JOB NO. 7597, PLAN NO. P-726

STREET IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM TOTAL
1.	Provide traffic control.	LS	1	\$	\$
2.	Remove and construct curb ramp approach and install cast-in-place truncated domes per SPPWC Std. Plan No. 111-5.	EA	36	\$	\$
3.	Remove and construct 4-inch thick PCC sidewalk over compacted native per SPPWC Standard Plan 113-2.	SF	15,000	\$	\$
4.	Remove and construct 4-inch thick PCC Residential driveway approach over compacted native STD. Plan 113-2.	SF	7,500	\$	\$
5.	Remove and construct 8-inch thick PCC curb and gutter per SPPWC Standard Plan 120-2 or match existing.	LF	3,200	\$	\$
6.	Remove and construct longitudinal gutter per SPPWC Standard Plan 122-2.	SF	2,300	\$	\$
7.	Cold Mill 1.5-inch existing AC Pavement.	SF	226,000	\$	\$
8.	Construct 1.5-inch AC pavement ARHM-GG-C (PG64-16).	TONS	2,100	\$	\$
9.	Adjust existing water and irrigation valve box and cover to grade.	EA	8	\$	\$
10.	Adjust existing utility valve (water and gas) to grade.	EA	28	\$	\$
11.	Adjust manhole frame and cover to grade per SPPWC Std. Plan No. 205-2.	EA	18	\$	\$
12.	Furnish and Install signing, striping and paint all house numbers within project limits.	LS	1	\$	\$
13.	Construct slurry seal.	SF	35,000	\$	\$
14.	Re-establish survey monumentation.	EA	5	\$	\$
SUBTOTAL ITEMS 1-14					\$

WATER IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM TOTAL
15.	Provide traffic control.	LS	1	\$	\$
16.	Furnish and install new 1" water service connection (City furnished meter) & meter box, including connection to the existing building water supply, potholing, pavement replacement, tunneling, removal of existing facilities, as necessary and all appurtenant work complete per San Fernando Water Construction Standard Plate No. 19 and Specifications.	EA	154	\$	\$
17.	Furnish and install new 8" diameter D.I.P. (Class 350) Water Pipeline, including potholing, connection to the existing water main, fittings, pavement replacement, tunneling, removal of existing facilities, as necessary and appurtenant complete.	LF	2,000	\$	\$
18.	Furnish and install 6" resilient wedge gate valve, fittings, removal of existing facilities, as necessary, and all appurtenant work complete.	EA	1	\$	\$
19.	Furnish and install 8" resilient wedge gate valve, fittings, removal of existing facilities, as necessary, and all appurtenant work complete.	EA	9	\$	\$
20.	Connect existing fire hydrant line to main.	EA	1	\$	\$
21.	Furnish and install 6" fire hydrant, including ductile iron bury, valves, fittings, potholing, pavement replacement, removal of existing facilities, as necessary, and all appurtenant work complete.	EA	9	\$	\$
SUBTOTAL ITEMS 15-21					\$

SEWER IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM TOTAL
22.	Provide traffic control	LS	1	\$	\$
23.	Provide pre-construction closed circuit television (CCTV) inspection.	LS	1	\$	\$
24.	Provide post-construction closed circuit television (CCTV) inspection.	LS	1	\$	\$

SEWER IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	ITEM TOTAL
25.	Provide clearing of sewer line, as necessary and appurtenant complete.	LS	1	\$	\$
26.	Furnish and install pipe sleeve for the existing 8-inch VCP sewer main, including potholing, fittings, pavement replacement, flow diversion, removal of existing facilities, as necessary and appurtenant complete.	LF	220	\$	\$
27.	Furnish and install CIPP sewer Lining for the existing 8-inch VCP sewer main, including potholing, fittings, flow diversion, removal of existing facilities, as necessary and appurtenant complete.	LF	2,300	\$	\$
SUBTOTAL ITEMS 22-27					\$
TOTAL BID AMOUNT 1-27					\$

The bidder acknowledges receipt of the following addendum issued for the above project. If no addendum has been received, write "None".

List of Addendum Received: _____

The City does not expressly or by implication agree that the actual amount of work will correspond with the foregoing quantities, but reserves the right to increase or decrease the amount of any class or portion of the work or to omit portions of the work as may be deemed necessary or advisable by the Engineer

The bidder further agrees that in case of not executing the required contract with necessary bonds within ten (10) days, not including Sundays, after having received notice that the contract is ready for signature, the proceeds of the check or bond accompanying his bid shall become the property of the City of San Fernando.

By submission of the Contractor's Proposal, the bidder also certifies that the bid is a balanced bid.