CITY OF SAN FERNANDO PUBLIC WORKS DEPARTMENT SAN FERNANDO REGIONAL PARK INFILTRATION PROJECT SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD JOB NO.7601 PLAN NO.P-732

NOTES TO CONTRACTOR

ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CITY OF SAN FERNANDO REQUIREMENTS.

THE CONTRACTOR SHALL TAKE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER UTILITIES NOT OF RECORD OR NOT SHOWN ON THESE PLANS.

ALL WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE AGENCY'S STANDARD PLANS, PROJECT PLANS, SPECIFICATIONS, AND CONTRACT DOCUMENTS. THE CONTRACTOR SHALL KEEP A COPY OF THIS INFORMATION ON THE JOBSITE. A PRECONSTRUCTION MEETING SHALL BE HELD A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK.

THE CONTRACTOR SHALL NOTIFY THE AGENCY'S CONSTRUCTION MANAGER, MANUEL FABIAN @ (818) 898-1243, A MINIMUM OF 5 WORKING DAYS PRIOR TO THE START OF CONSTRUCTION AND 48 HOURS IN ADVANCE OF INSPECTION REQUESTS.

PROJECT STATIONING REFERS TO THE CENTERLINE OF THE STORM DRAIN, UNLESS INDICATED OTHERWISE.

STOCK PILING OF EXCESS REMOVED MATERIAL WILL NOT BE ALLOWED IN OR AROUND THE PROJECT SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAULING OFF ALL EXCESS MATERIALS GENERATED DURING THE CONSTRUCTION OF THIS PROJECT TO AN APPROVED DISPOSAL SITE.


DUST SHALL BE CONTROLLED WITH WATER OR AS REQUIRED UNDER THE DIRECTION OF THE INSPECTOR.

REMOVAL OF ALL VEGETATION AND DEBRIS PRIOR TO ANY GRADING IS REQUIRED.

NO EXCAVATION SHALL BE LEFT OPEN AFTER DAYLIGHT HOURS WITH THE EXCEPTION OF THE SUBSURFACE INFILTRATION SYSTEM, EXCAVATIONS SHALL BE BACKFILLED AND PAVEMENT REPLACED OR BRIDGED WITH TRAFFIC RATED STEEL PLATES. CONTRACTOR SHALL WORK FROM 7:00 AM TO 4:00 PM MONDAY THRU FRIDAY, EXCLUDING HOLIDAYS, UNLESS OTHERWISE ACCEPTED BY THE CITY. ALL WORK WITHIN VEHICULAR TRAFFIC LANES SHALL BE LIMITED BETWEEN 9:00 AM AND 3:00 PM.

AN AGENCY APPROVED TRAFFIC CONTROL PLAN PER LATEST EDITION OF THE MANUAL SHALL BE SECURED BY THE CONTRACTOR 48 HOURS PRIOR TO CONSTRUCTION.

	PROJECT S			
		Image: Weight of the second	S` ♥ ♥ ♥ ♥ 0 0 ₪ 0 ↓ 0 -0 ♥	
NOTICE TO CONTRACTOR: T SHALL BE THE SOLE RESPONSIBILITY OF CALL THE USA UNDERGROUND ALERT FOR LO JNDERGROUND UTILITIES NO LESS THAN TW THAN SEVEN DAYS PRIOR TO CONSTRUCTION 811 THE CONTRACTOR SHALL ASSUME SOLE RESP DAMAGE DONE TO EXISTING UTILITIES OR STF NCLUDING CONCRETE/LANDSCAPING DURING	PONSIBILITY FOR ANY REET IMPROVEMENTS	"FUNDING FOR THIS PROJECT HAS BEEN PROVIDED IN FULL OR IN PART THROUGH AN AGREEMENT WITH THE STATE WATER RESOURCES CONTROL BOARD USING FUNDS FROM PROPOSITION 1. THE CONTENTS OF THIS DOCUMENT DO NOT NECESSARILY REFLECT THE VIEWS AND POLICIES OF THE FOREGOING, NOR DOES MENTION OF TRADE NAMES OR COMMERCIAL PRODUCTS CONSTITUTE ENDORSEMENT OR RECOMMENDATION FOR USE."	— — Е — — — — — — G — · · · — — 0 — — — (ОН) — — SD — — · · · · — Т — · · · — — W — — — — Х —	- OIL - OVERHEAD - SEWER - STORM DRA - TELEPHONE
UNDERGROUND SERVICE ALERT CALL: TOLL FREE 811 TWO WORKING DAYS BEFORE YOU DIG	REV. DATE BY	DESCRIPTION	APP'V'D	ARED BY:



SCALE: 1"=500' T.G. PAGE 502-B1, 482-B7, 482 C-7

PUBLIC UTILITIES AND AGENCIES WITHIN THE CITY OF SAN FERNANDO

RING	COMPANY	CONTACT	PHONE NO.	
E HYDRANT HT POLE NHOLE WER POLE	WATER	CITY OF SAN FERNANDO 120 MACNEIL ST. SAN FERNANDO, CA 91340 DANNY GARCIA	818 898 1293	
L BOX N FFIC SIGNAL BOX	WASTEWATER	CITY OF SAN FERNANDO 120 MACNEIL ST. SAN FERNANDO, CA 91340 DALE WARREN	818 898 1293	
TER METER	ELECTRICITY	SOUTHERN CALIFORNIA EDISON COMPANY EMERGENCY CALLS	800 611 1911	
ER VALVE JLT	GAS	SOUTHERN CALIFORNIA GAS COMPANY EMERGENCY CALLS	800 427 2200	
CTRICAL	OIL	PLAINS ALL AMERICAN PIPELINE EMERGENCY CALLS	800 987 4737	
	TELEPHONE	FRONTIER COMMUNICATIONS EMERGENCY CALLS	800 921 8101	
ERHEAD LINE VER	,	SPECTRUM EMERGENCY CALLS	818 700 6500	
DRM DRAIN EPHONE	CABLE / COMMUNICATION	CENTURY LINK AND LEVEL 3 NETWORK EMERGENCY CALLS	918 547 0007	
FER Y BOUNDARY		CHARTER COMMUNICATIONS EMERGENCY CALLS	818 922 6167	
AIN LINK FENCE HT-OF-WAY	POLICE	CITY OF SAN FERNANDO POLICE DEPT. NON-EMERGENCY NUMBER	818 898 1267	



1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com

ROFESSIONAL RUN L. 44				Moun		
				Matthew Baumgardner,		DATE
No.85752				Director of Public Works		
pangeful !!				R.C.E. NO.: <u>71932</u> E	XP. DATE: <u>12/3</u>	31 /202
★\'Exp. <u>9/30/2022</u> /★				<u></u>		17202
CIVIL ONT	DRAWN BY:	TT	APR 2021	/a/ /		
OF CALIFOR	DESIGNED BY:	KH	APR 2021	-/ -/ //		
	CHECKED BY:	VB	APR 2021	Manuel Fabian, Civil Engi	neer Assistant II	DATE



SHEET LIST TABLE

SHT. NO.	DRAWING NO.	SHEET TITLE						
1	T-01	TITLE SHEET						
2	C-01	GENERAL NOTES						
3	C-02	LINE "A1" AND "A2" PLAN AND PROFILE AND SUBSURFACE INFILTRATION SYSTEM PLAN						
4	C-03	LINE "B" STA 10+00 TO 13+50 PLAN AND PROFILE						
5	C-04	LINE "B" STA 13+50 TO 20+00 PLAN AND PROFILE						
6	C-05	LINE "B" STA 20+00 TO 26+50 PLAN AND PROFILE						
7	C-06	LINE "B" STA 26+50 TO 33+00 PLAN AND PROFILE						
8	C-07	LINE "B" STA 33+00 TO 37+00 PLAN AND PROFILE						
9	C-08	LINE "B" STA 37+00 TO 41+00 PLAN AND PROFILE						
10	C-09	LINE "B" STA 41+00 TO 47+50 PLAN AND PROFILE						
11	C-10	LINE "B" STA 47+50 TO 53+00 PLAN AND PROFILE						
12	C-11	LINE "B" STA 53+00 TO 54+23 PLAN AND PROFILE						
13	C-12	PRETREATMENT UNIT						
14	C-13	SUBSURFACE INFILTRATION SYSTEM PLAN AND DETAILS						
15	C-14	SUBSURFACE INFILTRATION SYSTEM SECTION						
16	C-15	SUBSURFACE INFILTRATION SYSTEM DETAILS						
17	C-16	DETAILS						
18	C-17	DETAILS						
19	C-18	SEWER PLAN						
20	C-19	STREET IMPROVEMENT PLAN STA 10+00 TO 23+12						
21	C-20	STREET IMPROVEMENT PLAN STA 27+47 TO 40+14						
22	C-21	STRIPING PLAN STA 10+00 TO 23+12						
23	C-22	STRIPING PLAN STA 27+47 TO 40+14						
24	E-01	GENERAL NOTES, ELECTRICAL SYMBOLS, SCHEMATIC SYMBOLS, ABBREVIATIONS						
25	E-02	FIRST STREET DIVERSION SINGLE LINE DIAGRAM, LOAD SUMMARY AND SCHEDULES						
26	E-03	FIRST STREET DIVERSION ELECTRICAL PLANS						
27	E-04	FIRST STREET DIVERSION CONTROL PANEL ELEVATION AND COMPONENT SCHEDULE						
28	E-05	PIPING & INSTRUMENTATION DIAGRAM						
29	E-06	GLENOAKS BLVD. DIVERSION SINGLE LINE DIAGRAM, LOAD SUMMARY AND PANEL SCHEDULES						
30	E-07	GLENOAKS BLVD. DIVERSION ELECTRICAL PLAN						
31	E-08	GLENOAKS BLVD. DIVERSION METER PEDESTAL ELEVATION AND COMPONENT SCHEDULE						
32	E-09	TYPICAL CONTROL SCHEMATIC DIAGRAM & CONDUIT SCHEDULE						
33	E-10	ELECTRICAL DETAILS						
34	E-11	PIPING & INSTRUMENTATION DIAGRAM						
35	EC-01	EROSION CONTROL PLAN						
36	EC-02	EROSION CONTROL PLAN STA 10+00 TO 12+40						
37	EC-03	EROSION CONTROL PLAN STA 12+40 TO 16+00						
38	EC-04	EROSION CONTROL PLAN STA 16+00 TO 35+75						
39	EC-05	EROSION CONTROL PLAN STA 35+75 TO 54+23						
40	LS-01	LANDSCAPE LAYOUT PLAN						
41	LS-02	PLANTING PLAN						
42	LS-03	PLANTING AND SIGN DETAILS						
43	LS-04	IRRIGATION PLAN						
44	LS-05	IRRIGATION DETAILS						
45	BL-01	BORING LOGS						
46	BL-02	BORING LOGS						

STY OF	San Fernando Regional Park Infiltration Project
SAN FERNANDO	SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD
HISTORIC & VISIONARY	TITLE SHEET

TITLE SHEET

CITY OF SAN FERNANDO DEPARTMENT OF PUBLIC WORKS

SHEET NO. 46

DWG No.

T-01

OF

NOTICE TO CONTRACTORS

- 1. SPECIFICATIONS: ALL WORK SHALL CONFORM TO THE LATEST EDITION AND SUPPLEMENTS OF "THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION" (GREENBOOK).
- 2. THIS IMPROVEMENT CONSISTS OF WORK CALLED FOR ONLY ON THIS PLAN.
- 3. TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE "WORK AREA TRAFFIC CONTROL HANDBOOK" (WATCH).
- 4. REMOVALS: REMOVE ALL EXISTING IMPROVEMENTS THAT INTERFERE WITH THE CONSTRUCTION OF THIS PROJECT. ALL UTILITIES OWNED BY ENTITIES OTHER THAN THE CITY SHALL BE REMOVED OR RELOCATED BY THEIR OWNER. B. CONTRACTOR TO REMOVE AND RELOCATE CITY-OWNED UTILITIES SHOWN IN THESE PLANS.
- 5. IN ADDITION TO THE RECONSTRUCTION OF PAVEMENT SHOWN HEREON, WORK REQUIRED UNDER THESE PLANS WILL ALSO INCLUDE THE CONSTRUCTION OF PERMANENT TRENCH RESURFACING IN AREAS WHERE STORM DRAIN LINES HAVE BEEN INSTALLED TO SERVE THIS PROJECT. CONDITIONS OF TRENCH BACKFILL AND RESURFACING SHALL BE AS SHOWN ON SHEET C-17 AND SPECIFIED ON THE EXCAVATION PERMIT OBTAINED BY THE CONTRACTOR. PAVING OF ROADWAY AREAS SHALL BE WITHHELD UNTIL CONTEMPLATED UTILITY CHANGES OR INSTALLATIONS HAVE BEEN MADE UNDER CITY PERMIT.
- 6. REPAIR AND/OR REPLACE ANY EXISTING BROKEN OR OFF-GRADE PAVEMENT, CONCRETE CURB, GUTTER OR SIDEWALK IMMEDIATELY ADJACENT TO OR WITHIN THE AREA OF THIS IMPROVEMENT SATISFACTORY TO THE CITY ENGINEER.
- 7. CONFIRM DEMO AND RELOCATION OF IRRIGATION LINES AND OTHER APPURTENANCES WITHIN PARK WITH THE CITY ENGINEER. 8. UNAUTHORIZED CHANGES AND USES: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR. OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS AND THE CITY.
- 9. PLANS ARE NOT TO BE UTILIZED UNLESS STAMPED "APPROVED" BY THE ENGINEER OF RECORD.
- 10. CONTRACTOR SHALL PROVIDE TIMELY NOTIFICATION TO THE ENGINEER OF RECORD OF ANY POTENTIAL OR ACTUAL DISCREPANCIES BETWEEN CIVIL PLANS AND OTHER PLANS/ACTUAL FIELD CONDITIONS.
- 11. ELEVATIONS INDICATED MAY HAVE BEEN INTERPOLATED FROM EXISTING TOPOGRAPHIC OR RECORD MAPS, CONTRACTOR SHALL FIELD VERIFY ELEVATIONS AND LOCATIONS WHERE PROPOSED IMPROVEMENTS JOIN EXISTING.
- 12. NOT ALL UTILITIES MAY BE SHOWN, CONTRACTOR SHALL FIELD VERIFY ELEVATIONS AND LOCATIONS OF ALL AFFECTED UTILITIES. FOR ALL CITY OWNED UTILITIES, PROTECT IN PLACE, RELOCATE, OR REPLACE AS NECESSARY ONCE APPROVED BY THE CITY ENGINEER. PROVIDE TEMPORARY UTILITY SERVICES AS NECESSARY. NOTIFY OWNER OF UTILITIES OWNED BY ENTITIES OTHER THAN THE CITY IF RELOCATION OR REPLACEMENT IS NECESSARY TO PERFORM REQUIRED IMPROVEMENTS.
- 13. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS, INSTALLATION DRAWINGS, CATALOG CUT-SHEETS, PRODUCT SPECIFICATIONS, AND OTHER APPLICABLE SUBMITTALS, IN A TIMELY MANNER, TO THE ENGINEER FOR APPROVAL.
- 14. WHERE EXISTING WATER SERVICES OR SEWER LATERALS ARE TO BE UTILIZED, CONTRACTOR SHALL FIELD VERIFY THE LOCATIONS AND FUNCTIONALITY OF SUCH SERVICES OR LATERALS.
- 15. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO FACILITIES.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE TO SECURE AND PAY FOR ALL NECESSARY CONSTRUCTION LAYDOWN AREAS.
- 17. THE CONTRACTOR SHALL ASSUME ALL RESPONSIBILITIES OF RENTING OPERATING EQUIPMENTS.
- 18. ALL REPAIRS TO CONSTRUCTION LAYDOWN AREAS AND TEMPORARY IMPROVEMENTS SHALL BE INSPECTED AND APPROVED BY THE INSPECTOR.
- 19. THE CONTRACTOR SHALL REMOVE, REGRADE, AND WHEN NECESSARY, BACKFILL TO RESTORE THE CONSTRUCTION LAYDOWN ACCESS AND TEMPORARY IMPROVEMENTS TO ITS ORIGINAL/FORMER CONDITION AT THE COMPLETION OF THE WORK.
- 20. THE CONTRACTOR SHALL BACKFILL EXCAVATED AREAS WITH ENGINEERED FILL UP TO THE ORIGINAL GRADE, UNLESS OTHERWISE SPECIFIED OR INDICATED ON THESE PLANS.
- 21. THE CONTRACTOR SHALL VERIFY ALL DIMENSION AND CONDITIONS IN THE FIELD PRIOR TO STARTING ANY WORK.
- 22. SURVEY MONUMENT PRESERVATION IS REQUIRED AND SHALL INCLUDE SUBMITTAL OF PRE AND POST CONSTRUCTION SURVEY MONUMENT TIES TO THE ENGINEER.
- 23. THE CONTRACTOR SHALL MAINTAIN LOCAL AND EMERGENCY ACCESS AT ALL TIMES.
- 24. NO CONSTRUCTION DEBRIS WILL BE ALLOWED TO FALL IN TO THE CATCH BASIN OR STORM DRAIN, IF ANY MATERIAL IS INADVERTENTLY INTRODUCED, THEN IT SHALL BE REMOVED IMMEDIATELY.
- 25. THE CONTRACTOR SHALL CONTACT AND COORDINATE WITH ALL UTILITY COMPANIES RESPONSIBLE FOR WORK TO BE PERFORMED NEAR THEIR RESPECTIVE FACILITIES. IN THE EVENT THAT THE CONTRACTOR'S OPERATION REQUIRES UTILITY RELOCATION IN ADDITION TO THAT SPECIFIED ON THE PLAN, SUCH ADDITIONAL WORK SHALL BE AT CONTRACTOR'S EXPENSE.
- 26. ALL CONCRETE AND SOIL NOT UTILIZED IN CONSTRUCTION SHALL BE DISPOSED OF IN ACCORDANCE WITH THE APPLICABLE JURISDICTION REGULATION.

CONCRETE REMOVAL NOTES:

WHERE REINFORCEMENT IS REQUIRED TO EXTEND THROUGH THE NEW JOINT, CONCRETE SHALL BE REMOVED IN THE FOLLOWING SEQUENCE.

- 1. A SAWCUT SHALL BE MADE ONE AND ONE-HALF INCHES DEEP AT THE REMOVAL LIMITS. CARE SHALL BE EXERCISED IN SAWING AT THE REMOVAL LIMITS SO AS NOT TO CUT THE REINFORCING STEEL IN THE REMAINING SLAB. THE EXISTING REINFORCING STEEL SHALL BE RETAINED AND EXTENDED INTO THE NEW CONSTRUCTION AS INDICATED ON THE PLANS.
- 2. USING HANDHELD EQUIPMENT, THE CONCRETE SHALL BE CAREFULLY REMOVED FOR THE FULL DEPTH OF THE WALL OR SLAB AND FOR A MINIMUM DISTANCE FROM THE SAWCUT EQUAL TO THE LONGEST EXTENSION OF THE EXISTING BARS TO BE EXTENDED INTO THE NEW CONSTRUCTION. THIS EXTENSION SHALL BE 30 BAR DIAMETERS, UNLESS OTHERWISE SHOWN.
- 3. EXISTING REINFORCEMENT SHALL BE CUT TO THE REQUIRED BAR EXTENSION.
- 4. THE REMAINING CONCRETE SHALL BE REMOVED BY ANY SUITABLE METHOD UPON APPROVAL OF THE ENGINEER, WHO SHALL BE THE SOLE JUDGE OF THE USE OF ANY CONCRETE REMOVAL EQUIPMENT. WRECKING BALLS OR OTHER SIMILAR DEVICES, WHICH ARE LIKELY TO DAMAGE THE CONCRETE TO BE LEFT IN PLACE, SHALL NOT BE USED.

NOTICE TO CONTRACTOR:			
IT SHALL BE THE SOLE RESPONSIBILITY OF THE CALL THE USA UNDERGROUND ALERT FOR LOCUNDERGROUND UTILITIES NO LESS THAN TWO THAN SEVEN DAYS PRIOR TO CONSTRUCTION.	CATION	I OF EX	(ISTING
811			
THE CONTRACTOR SHALL ASSUME SOLE RESPO DAMAGE DONE TO EXISTING UTILITIES OR STRE INCLUDING CONCRETE/LANDSCAPING DURING C	ET IM	PROVEN	IENTS
UNDERGROUND SERVICE ALERT			
FEORE		- · · ·	

UNDERGROUND SERVICE ALERT	REVISIONS	PREPARED BY:	PROFESSIONA	MElen	
CALL: TOLL FREE	DESCRIPTION APP'V'D	1561 E. ORANGETHORPE AVE. SUITE 240	AND REST AND		
811		SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com	* Exp. <u>9/30/2022</u> *	R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
TWO WORKING DAYS BEFORE YOU DIG			CIVIL DRAWN BY: TT APR 2021 DESIGNED BY: KH APR 2021 CHECKED BY: VB APR 2021		

POLLUTION PREVENTION NOTES

IN ORDER TO MEET THE REQUIREMENTS OF THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PROGRAM FOR CONSTRUCTION, CONSTRUCTION CONTRACTORS SHALL INSTALL AND MAINTAIN APPROPRIATE BEST MANAGEMENT PRACTICES (BMPS), AS SHOWN IN THE EROSION AND SEDIMENT CONTROL PLAN. ON ALL CONSTRUCTION PROJECTS, BMPS SHALL BE INSTALLED IN ACCORDANCE WITH INDUSTRY RECOMMENDED STANDARDS, AND/OR IN ACCORDANCE WITH ANY GENERAL CONSTRUCTION PERMIT ISSUED BY THE STATE FOR THE PROJECT TO PREVENT ANY DISCHARGES FROM THE PROJECT SITE OR INTO ANY STORM DRAIN FACILITIES. ALL SEDIMENTS, CONSTRUCTION MATERIALS, DEBRIS AND WASTES, AND OTHER POLLUTANTS MUST BE RETAINED ON SITE AND MAY NOT BE TRANSPORTED FROM THE SITE VIA SHEET FLOW, SWALES, AREA DRAINS, NATURAL DRAINAGE COURSES, WIND, OR VEHICLE TRACKING. UNDER DIRECTION OF THE ENGINEER OF RECORD, EROSION AND/OR SEDIMENT CONTROL DEVICES SHALL BE MODIFIED AS NEEDED AS THE PROJECT PROGRESSES TO ENSURE EFFECTIVENESS.

SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONSTRUCTION ENTRANCE ROADWAYS SHALL BE STABILIZED SO AS TO PREVENT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC ROADS. DEPOSITIONS MUST BE SWEPT UP IMMEDIATELY AND MAY NOT BE WASHED DOWN BY RAIN OR OTHER MEANS INTO THE STORM DRAIN SYSTEM.

1. STABILIZED CONSTRUCTION ENTRANCE SHALL BE:

A. LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING CONSTRUCTION SITE OR FROM A PUBLIC RIGHT OF WAY, STREET, ALLEY, AND SIDEWALK OR PARKING AREA.

B. SERIES OF STEEL PLATES WITH "RUMBLE STRIPS", AND/OR MIN 4" COARSE AGGREGATE WITH LENGTH, WIDTH, & THICKNESS AS NEEDED TO ADEQUATELY PREVENT ANY TRACKING ONTO PAVED SURFACES.

2. ADDING A WASH RACK WITH A SEDIMENT TRAP LARGE ENOUGH TO COLLECT ALL WASH WATER CAN GREATLY IMPROVE EFFICIENCY.

3. ALL VEHICLES ACCESSING THE CONSTRUCTION SITE SHALL UTILIZE THE STABILIZED CONSTRUCTION ENTRANCE SITES.

STREET MAINTENANCE NOTES

4. REMOVE ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS IMMEDIATELY.

5. SWEEP PAVED AREAS THAT RECEIVE CONSTRUCTION TRAFFIC WHENEVER SEDIMENT BECOMES VISIBLE.

6. PAVEMENT WASHING WITH WATER IS PROHIBITED IF IT RESULTS IN A DISCHARGE TO THE STORM DRAIN SYSTEM.

NPDES NOTES

7. CONSTRUCTION SITE BMPS FOR THE MANAGEMENT OF STORMWATER AND NON-STORMWATER DISCHARGES SHALL BE DOCUMENTED ON THE EROSION CONTROL PLAN. THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) MUST BE RETAINED ON THE JOBSITE THROUGHOUT THE HOURS OF CONSTRUCTION. THE IMPLEMENTATION AND MAINTENANCE OF THE SITE BMPS IS REQUIRED TO MINIMIZE JOBSITE EROSION AND SEDIMENTATION. ARRANGEMENTS SHALL BE MADE BY THE CONTRACTOR TO MAINTAIN THOSE BMPS THROUGHOUT THE TIME OF CONSTRUCTION.

8. EROSION CONTROL BMPS SHALL BE IMPLEMENTED AND MAINTAINED TO PREVENT AND/OR MINIMIZE THE ENTRAINMENT OF SOIL IN RUNOFF FROM DISTURBED SOIL AREAS ON CONSTRUCTION SITES.

9. SEDIMENT CONTROL BMPS SHALL BE IMPLEMENTED AND MAINTAINED TO PREVENT AND/OR MINIMIZE THE TRANSPORT OF SOIL FROM THE CONSTRUCTION SITE.

10. AREAS THAT ARE CLEARED AND GRADED SHALL BE LIMITED TO ONLY THE PORTION OF THE SITE THAT IS NECESSARY FOR CONSTRUCTION. THE CONSTRUCTION SITE SHALL BE MANAGED TO MINIMIZE THE EXPOSURE TIME OF DISTURBED SOIL AREAS THROUGH PHASING AND SCHEDULING OF GRADING AND THE USE OF TEMPORARY AND PERMANENT SOIL STABILIZATION.

11. STOCKPILES OF SOIL AND SEDIMENTS FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE PROPERLY CONTAINED TO ELIMINATE OR REDUCE SEDIMENT TRANSPORT FROM THE SITE OR STREETS, DRAINAGE FACILITIES OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING, OR WIND.

12. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AFFECTED CATCH BASINS WITH APPROPRIATE INLET PROTECTION (INCLUDING FILTER FABRIC AND GRAVEL BAGS) AND ENSURE THAT ALL SEDIMENT, DIRT, AND MATERIALS FROM THE CONSTRUCTION SITE DO NOT ENTER THE CATCH BASINS.

13. ALL STORM INLETS PROTECTED BY INLET PROTECTION SHALL BE MAINTAINED AND MODIFIED AS REQUIRED DURING CONSTRUCTION.

14. ANY SEDIMENT FROM CONSTRUCTION THAT IS BLOCKING DRAINAGE INLETS AND CREATES STANDING WATER ON ROADWAYS AND/OR DRIVEWAYS SHALL BE REMOVED IMMEDIATELY.

EROSION CONTROL NOTES

15. APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SOIL DISTURBANCE. MEASURES SHALL BE TAKEN TO CONTROL EROSION WITHIN THE PROJECT AREA. SEDIMENT IN RUNOFF WATER SHALL BE TRAPPED AND RETAINED WITHIN THE PROJECT AREA.

16. MINIMIZE SOIL EROSION AND CONTROL SEDIMENTATION DURING CONSTRUCTION.

17. PROTECT AND MANAGE ON AND OFF-SITE MATERIAL STORAGE AREAS (OVERBURDEN AND STOCKPILES OF DIRT, BORROW AREAS, OR OTHER AREAS USED SOLELY BY THE PERMITTED PROJECT ARE CONSIDERED A PART OF THE PROJECT).

18. SOIL STOCKPILES MUST BE STABILIZED OR COVERED AT THE END OF EACH WORKDAY. ALL STOCKPILES SHALL BE SURROUNDED BY SEDIMENT CONTROLS.

19. DIVERT UNCONTAMINATED WATER AROUND DISTURBED AREAS.

20. AFTER A RAINSTORM, ALL SILT AND DEBRIS SHALL BE REMOVED FROM STREETS, CHECK BERMS, AND CATCH BASINS.

21. PROPERLY MANAGE ON-SITE CONSTRUCTION AND WASTE MATERIALS.

STANDARD PLANS

(2012 EDITION & REVISIONS)

111-5	CURB RAMP
120-2	CURB AND GUTTER
171-0	PAVEMENT MARKINGS – ARRO
172-0	STOP AND STOP BAR
320-2	MANHOLE PIPE TO PIPE
321-2	MANHOLE PIPE TO PIPE
324-2	MANHOLE SHAFT - WITH ECCI
326-2	MANHOLE SHAFT - 36" (900r
331–3	JUNCTION STRUCTURE - PIPE
630-4	24" MANHOLE FRAME AND CO
636-2	POLYPROPYLENE - PLASTIC S

COORDINATE DATUM

1983 NAD.

BENCHMARK

LOS ANGELES COUNTY BENCHMARK 03-02219 ELEV.1058.613 FEET NAVD88 P.K. FOUND NAIL IN LEAD N.W. CURB WOLFSKILL ST: 30.4FT NE/O BCR NE/O SAN FERNANDO RD.

STANDARD PLANS FOR PUBLIC CONSTRUCTION (SPPWC)

OWS AND SYMBOLS

CENTRIC REDUCER Omm) WITHOUT REDUCER E TO PIPE OVFR POLYPROPYLENE - PLASTIC STEP MISCELLANEOUS STRUCTURES


COORDINATES SHOWN ARE BASED ON THE CALIFORNIA STATE PLANE COORDINATE SYSTEM, ZONE V,




San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

GENERAL NOTES

DWG No. C-01 SHEET NO. OF 46






UNDERGROUND SERVICE ALERT	REVISIONS						
BEFORE PO	REV. D	ATE	BY	DESCRIPTION APP'V'D			
CALL: TOLL FREE							
811							
TWO WORKING DAYS BEFORE YOU DIG							

CONSTRUCTION NOTES:

1 PROTECT IN PLACE 11 REMOVE AND REINSTALL INTERFERING PORTIONS OF 6' HIGH CHAIN LINK FENCE 12 18" RCP AND BEDDING PER DETAIL 1 ON SHEET 18 13 STORM DRAIN MANHOLE PER SPPWC STD. PLAN NO. 321–2

NOTES TO CONTRACTOR:


- 1. CONTRACTOR TO REMOVE AND REPLACE IRRIGATION LINES AND APPURTENANCES WITHIN THE PARK AS SHOWN ON IRRIGATION PLANS
- CONTRACTOR TO REMOVE AND REPLACE ELECTRICAL LINES AND APPURTENANCES WITHIN THE PARK IN ASSOCIATION WITH THE IRRIGATION SYSTEM INDICATED ABOVE
 RESTORE SITE TO ORIGINAL LINE AND GRADE
- 4. SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY
- 5. ENCASE EXISTING PIPE IN CONCRETE IF THE PIPE IS LESS THAN 3 FEET FROM PROPOSED IMPROVEMENTS



San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD


> LINE "B" STA 10+00 TO 13+50 PLAN AND PROFILE

DWG NO. C-03 SHEET NO. 4 OF 46





\sim	\bigvee					L	
						Γ	
ΓWΟ	WORKING	DAYS	BEFORE	YOU	DIG	Γ	

Σ	1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526–7500	× Exp. 9/30/2022 ★				Matthew Baumgardner, DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
	www.cwecorp.com	CIVIL CIVIL	DRAWN BY:	TT	APR 2021	pall	
		E OF CALIFOR	DESIGNED BY:	КН	APR 2021		
			CHECKED BY:	VB	APR 2021	Manuel Fabian, Civil Engineer Assistant II DATE	




UNDERGROUND SERVICE ALERT	REVISIONS							
BEFORE FOR	REV. DA	E BY	DESCRIPTION	APP'V'D				
CALL: TOLL FREE								
811								
TWO WORKING DAYS BEFORE YOU DIG								





NUCREASE REPORT NOT REPORT	



CONSTRUCTION NOTES:

(1) PROTECT IN PLACE

12-18" RCP AND BEDDING PER DETAIL 1 ON SHEET 18


(13) STORM DRAIN MANHOLE PER SPPWC STD. PLAN NO. 321-2


NOTES TO CONTRACTOR:


- 1. SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY
- 2. ENCASE EXISTING PIPE IN CONCRETE IF THE PIPE IS LESS THAN 3 FEET FROM PROPOSED IMPROVEMENTS

33+00 < ↓ ⊢ MATCHLINE - ST SEE SHEET


UNDERGROUND SERVICE ALERT		REVISIONS							
L BEFORE POL	REV.	DATE	BY	DESCRIPTION	APP'V'D				
CALL: TOLL FREE									
811									
TWO WORKING DAYS BEFORE YOU DIG									







	1095 —					
		Image:	S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0. S=0.		+00 39+50	S=1.00%
OPROTECT IN PLACE 1 PROTECT IN PLACE 12 18" RCP AND BEDDING PER DETAIL 1 ON SHEET 18 13 STORM DRAIN MANHOLE PER SPPWC STD. PLAN NO. 321-2 DETEST DECONTRACTORE 1 SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY 1 SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY 2 EXCASE EXISTING PIPE IN CONCRETE IF THE PIPE IS LESS THAN 3 FEET FROM PROPOSED IMPROVEMENTS	MATCHLINE - STA 37+00 SEE SHEET 8		<pre> 12" DIP WA 8" VCP SEV 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 12 1</pre>	ATER R/W 6 DIP WATER 1	30.0' 30.0' 30.0' 30.0' 30.0' MH (1) MH	8" DIP WATER 10 6" DIP WATER 12" OIL (ABANDONED) 12" OIL (ABANDONED) 114" OIL (STEEL) 14" OIL (STEEL) 14" OIL (STEEL) 14" OIL (STEEL) 13" PVC GAS STA 40+03.64 EC 30.0' 18" WATER 18" WATER
UNDERGROUND SERVICE ALERT VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE BII VINCUL TOLL FREE	INS CRIPTION	PREPARED BY:	1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com	DRAWN BY: CIVIL DF CALIFORNIA DESIGNED BY: CHECKED BY:	TT APR 2021 KH APR 2021 VB APR 2021 Manuel Fabian, Civil Engineer	DATE DATE DATE: <u>12/31/2021</u> Assistant II DATE



 $\widehat{\Box}$

<u>ATER</u> 39+7

5<u>1</u>

8" WATER STA: 39+57


91.(

51E

3" GAS STA: 39+09.0 6" WATER STA: 39+11.2

-EX. SURFACE

10" WAT STA: 39-STA: 39-STA: 39-RIM: 109







CITY OF SAN FERNANDO DEPARTMENT OF PUBLIC WORKS

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

> LINE "B" STA 37+00 TO 41+00 PLAN AND PROFILE


DWG NO. SHEET NO. 9 OF 46






FROM	PROPOSED	IMPROVEMENTS
------	----------	--------------

UNDERGROUND SERVICE ALERT		REVISIONS		PREPARED BY:		PROFESSIONA				Milen	
CALL: TOLL FREE 811	REV. DATE BY	DESCRIPTION	APP'V'D		1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500	× Exp. <u>9/30/2022</u> ★				Matthew Baumgardner, D/ Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/</u>	ATE 2021
TWO WORKING DAYS BEFORE YOU DIG					www.cwecorp.com	CIVIL OF CALIFORNIA	DRAWN BY: DESIGNED BY: CHECKED BY:	TT KH VB	APR 2021 APR 2021 APR 2021	Manuel Fabian, Civil Engineer Assistant II D.	ATE .






CONSTRUCTION NOTES:


1) PROTECT IN PLACE
(3) PRETREATMENT UNIT PER DETAIL ON SHEET 13
(12) 18" RCP AND BEDDING PER DETAIL 1 ON SHEET 18
13 STORM DRAIN MANHOLE PER SPPWC STD. PLAN NO. 321-2
(14) CURB RAMP PER STREET IMPROVEMENT PLAN SHEET 21
(15)
(16) Gate value, actuator, and vault per detail 3 on sheet 18
(17) - Electrical panel and box with concrete base per electrical plans

NOTES TO CONTRACTOR:

- 1. SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY
- 2. ENCASE EXISTING PIPE IN CONCRETE IF THE PIPE IS LESS THAN 3 FEET FROM PROPOSED IMPROVEMENTS

UNDERGROUND SERVICE ALERT		REVISIONS	PREPARED BY:		PROFESSIONAL			MEden		
CALL: TOLL FREE	REV. DATE BY	DESCRIPTION	APP'V'D	 1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 	No.85752			Matthew Baumgardner, Director of Public Works	DATE	Boltom A
811					★ Exp. <u>9/30/2022</u> ★			R.C.E. NO.: <u>71932</u> E	XP. DATE: <u>12/31/2021</u>	
TWO WORKING DAYS BEFORE YOU DIG					OF CALIFORNIU	DRAWN BY: DESIGNED BY: CHECKED BY:	KH APR	2021 2021 2021 Manuel Fabian, Civil Engin	neer Assistant II DATE	





CONSTRUCTION NOTES:


(1) PROTECT IN PLACE


(12)— 18" RCP AND BEDDING PER DETAIL 1 ON SHEET 18 (19) DROP MANHOLE AND DIVERSION STRUCTURE PER MODIFIED SPPWC STD. PLAN NO. 320-2 AS SHOWN HEREON

NOTES TO CONTRACTOR:

- 1. SUPPORT UTILITIES ACROSS TRENCHES AS NECESSARY
- 2. ENCASE EXISTING PIPE IN CONCRETE IF THE PIPE IS LESS THAN 3 FEET FROM PROPOSED IMPROVEMENTS


UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED BY:
BEFORE FOR	REV.	DATE	ΒY	DESCRIPTION APP'V	
CALL: TOLL FREE					
811					
TWO WORKING DAYS BEFORE YOU DIG					





DIVERSION STRUCTURE MODIFIED MANHOLE PER SPPWC 320-2 DETAIL SCALE: 1"=4'


Millen 1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 Matthew Baumgardner, Director of Public Works DATE ŇΞ R.C.E. NO.: 71932 EXP. DATE: 12/31/2021 xp. 9/30/2022 www.cwecorp.com APR 2021 DRAWN BY: /n/ APR 2021 DESIGNED BY: KH CHECKED BY: APR 2021 Manuel Fabian, Civil Engineer Assistant II DATE VB



~~ ™

Ň

NOTE: ALL STEEL SHALL BE 2" CLEAR UNLESS OTHERWISE NOTED






San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD


> LINE "B" STA 53+00 TO 54+23 PLAN AND PROFILE

DWG No. C-11 SHEET NO. 12 OF 46



SITE DESIGN DATA:									
WATER QUALITY FLOW RATE	9 CFS								
PEAK FLOW RATE	8.8 CFS								
RETURN PERIOD OF WATER QUALITY FLOW RATE	RAA EVENT								
MAKE AND MODEL (OR AGENCY APPROVED EQUAL)	JDS120-6748 OR CDS5640-10-C								

MATERIAL LIST											
COUNT	DESCRIPTION										
1	SEPARATION SCREEN										
1	SEALANT FOR JOINTS										
1	GRADE RINGS/RISERS										
3	30" Ø CAST IRON FRAME AND COVER, H20 RATED										
1	PRECAST CONCRETE MANHOLE STRUCTURE										




ŴE





APR 2021 DRAWN BY: APR 2021 DESIGNED BY: KH





GENERAL NOTES:

1. PRECAST CONCRETE JOINTS SHALL BE SEALED USING BUTYL RUBBER COMPOUND. 2. ALL PIPE PENETRATIONS SHALL BE GROUTED IN PRECAST CONCRETE OPENINGS.

SPECIFICATIONS:

- 1. PRECAST MATERIALS AND MANUFACTURING METHODS SHALL CONFORM TO ASTM C-478, C-857 AND LACSD S-A-206.
- 2. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH F'c = 5,000-psi AT 28-DAYS. 3. PORTLAND CEMENT USED IN THE PRECAST SECTION SHALL MEET THE REQUIREMENTS OF TYPE II/V HIGH SULFATE RESISTANT CEMENT IN ACCORDANCE WITH ASTM CLASS M C-150.
- 4. MANHOLE COMPONENTS CONFORM TO CURRENT SPECIFICATIONS, ASTM C-478, AND AASHTO M199.
- 5. STRUCTURE SHALL MEET ASSHTO HS-20 AND CASTINGS SHALL MEET HS20 (ASSHTO M 306) LOAD RATING. 6. ALL PRECAST CONCRETE COMPONENTS TO BE MANUFACTURED IN AN NPCA CERTIFIED PLANT.

DWG No. San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

PRETREATMENT UNIT

C-12 SHEET NO. 13 OF 46

				l		m				ш	
	IN										
											
	 "			1						·	
		I	I	1		I	I	1	I	I	
			I	1	1	I	1	1	I.	I.	
											- 4-8-
	▎▐		I	1		I	I	1	l I	I	
	"[I	1 I			1	1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	I		- A A
			I.			1	1	1	l I	I.	
											<u> </u>
] ⊪[
			l I	I	I						
	 [
						-	-	-			- 19-19-
					- 144 - 44		1	1	- 1 44 - 1	- 	- 44
-											.
			1 I				1				
	▎▐										
								I			
MH ACCESS SHAFT (TYP.)											
BURIÈD 4"	[- 14-18-
		I	· · · · · · · · · · · · · · · · · · ·	I		1	1	1 I I I I I I I I I I I I I I I I I I I	- 188 - 188 -	- 1 4-14 - 1	
	11										
	"[
	SDI										
	SPIV										
- 						176	-6 3/4"				
						.,					
	-								244'-5"		


- 244'-5" -


SUBSURFACE INFILTRATION SYSTEM


PLAN


SCALE: 1"= 20'


UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED BY:
CALL: TOLL FREE	REV.	DATE	BY	DESCRIPTION APP'V'D	
					i f V
811					
					-
TWO WORKING DAYS BEFORE YOU DIG					












- 6. DIMENSION OF SYSTEM ALLOW FOR A 3/4" GAP BETWEEN EACH MODULE.
- 7. ALL DIMENSIONS TO BE VERIFIED IN THE FIELD.
- 8. THE CONTROL JOINTS SHALL BE BETWEEN 16'-0" TO 24'-0" MAX APART.
- 9. SEE INSTALLATION SPECIFICATIONS HEREON





UNDERGROUND SERVICE ALERT		REVISIONS					
BEFORE POL	REV.	DATE	BY	DESCRIPTION APP	°'V'D		
CALL: TOLL FREE							
811							
TWO WORKING DAYS BEFORE YOU DIG							
TWO WORKING DAYS BEFORE YOU DIG							

INSTALLATION SPECIFICATIONS

1. SUBSURFACE INFILTRATION SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH ASTM C891, STANDARD FOR INSTALLATION OF UNDERGROUND PRECAST CONCRETE UTILITY STRUCTURES. THE FOLLOWING ADDITIONS AND/OR EXCEPTIONS SHALL APPLY: 2. PROPER/ADEQUATE EQUIPMENT IS USED TO SET/INSTALL THE MODULES.

3. MODULES CAN BE PLACED ON A LEVEL, 12" CONCRETE FOUNDATION OF STRUCTURAL BACKFILL WITH A 1'-O" OVERHANG ON ALL SIDES THAT SHALL BE POURED IN PLACE BY INSTALLING CONTRACTOR. A QUALIFIED GEOTECHNICAL ENGINEER WILL BE EMPLOYED, BY OWNER, TO PROVIDE ASSISTANCE IN EVALUATING THE EXISTING SOIL CONDITIONS TO ENSURE THAT THE SOIL BEARING PRESSURE MEETS OR EXCEEDS THE STRUCTURAL DESIGN LOADING CRITERIA AS SPECIFIED ON SHEET 15.


4. MODULES SHALL BE PLACED SUCH THAT THE MAXIMUM SPACE BETWEEN ADJACENT MODULES DOES NOT EXCEED $\frac{3}{4}$ " (SEE DETAIL 2). IF THE SPACE EXCEEDS $\frac{3}{4}$ ", THE MODULES SHALL BE RESET WITH APPROPRIATE ADJUSTMENT MADE TO LINE AND GRADE TO BRING

5. THE PERIMETER HORIZONTAL JOINT BETWEEN THE MODULES AND THE CONCRETE FOUNDATION SHALL BE SEALED TO THE FOUNDATION WITH PRE-FORMED MASTIC JOINT SEALER ACCORDING TO ASTM C891, 8.8 AND 8.12 (SEE DETAIL 1). THE MASTIC JOINT TAPE DOES NOT PROVIDE A WATERTIGHT SEAL. THE SOLE PURPOSE OF THE JOINT TAPE IS TO PROVIDE A SILT AND SOIL

6. ALL EXTERIOR JOINTS BETWEEN ADJACENT MODULES SHALL BE SEALED WITH 8" WIDE PRE-FORMED, COLD-APPLIED, SELF-ADHERING ELASTOMERIC RESIN, BONDED TO A WOVEN, HIGHLY PUNCTURE RESISTANT POLYMER WRAP, CONFORMING TO ASTM C891 AND SHALL BE INTEGRATED WITH PRIMER SEALANT AS APPROVED BY VENDOR (SEE DETAILS 3 & 4). THE JOINT WRAP DOES NOT PROVIDE A WATERTIGHT SEAL. THE SOLE PURPOSE OF THE JOINT WRAP IS TO PROVIDE A SILT AND SOIL TIGHT SYSTEM. THE ADHESIVE EXTERIOR JOINT WRAP SHALL BE INSTALLED ACCORDING TO THE FOLLOWING INSTALLATION INSTRUCTIONS:

6.1. USE A BRUSH OR WET CLOTH TO THOROUGHLY CLEAN THE OUTSIDE SURFACE AT THE POINT WHERE JOINT WRAP IS TO BE

6.2. A RELEASE PAPER PROTECTS THE ADHESIVE SIDE OF THE JOINT WRAP. PLACE THE ADHESIVE TAPE (ADHESIVE SIDE DOWN) AROUND THE STRUCTURE, REMOVING THE RELEASE PAPER AS YOU GO. PRESS THE JOINT WRAP FIRMLY AGAINST THE MODULÉ SURFACE WHEN APPLYING.




ACCESS OPENING SPECIFICATION


PIPE OPENING SPECIFICATION

- 2. CONNECTING PIPES SHALL BE INSTALLED WITH A 1'-0" CONCRETE COLLAR, AND AN AGGREGATE CRADLE FOR AT LEAST ONE PIPE LENGTH (SEE PIPE CONNECTION DETAIL). A STRUCTURAL GRADE CONCRETE OR HIGH STRENGTH, NON-SHRINK GROUT WITH A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI SHALL BE USED. 3. THE ANNULAR SPACE BETWEEN THE PIPE AND THE HOLE SHALL BE FILLED WITH HIGH STRENGTH NON-SHRINK GROUT.

PIPE INSTALLATION INSTRUCTIONS

- HIGH STRENGTH NON-SHRINK GROUT HIGH STRENGTH
- NON-SHRINK GROUT CONCRETE FOUNDATION |-






1. ALL OPENINGS MUST RETAIN AT LEAST 1'-0" OF CLEARANCE FROM THE END OF THE MODULE UNLESS NOTED OTHERWISE. ALL ACCESS OPENINGS TO BE LOCATED ON INSIDE LEG UNLESS OTHERWISE SPECIFIED.

2. STEPS SHALL BE PER SPPWC 636-2 AND ARE PROVIDED INSIDE ANY MODULE AS SHOWN IN THESE PLANS. THE HIGHEST STEP IN THE MODULE IS TO BE PLACED A DISTANCE OF 0.50' FROM THE INSIDE EDGE OF THE MODULES. ALL ENSUING STEPS SHALL BE PLACED WITH A MAXIMUM DISTANCE OF 1'-3" BETWEEN THEM. STEPS MAY BE MOVED OR ALTERED TO AVOID OPENINGS OR OTHER IRREGULARITIES IN THE MODULE. 3. LIFTING INSERTS SHALL BE RELOCATED TO AVOID INTERFERENCE WITH ACCESS OPENINGS OR THE CENTER OF GRAVITY OF THE MODULE AS NEEDED. 4. ACCESS OPENINGS SHALL BE RELOCATED TO AVOID INTERFERENCE WITH INLET AND/OR OUTLET PIPE OPENINGS SO PLACEMENT OF STEPS IS ATTAINABLE. 5. PRECAST ADJUSTING RINGS SHALL BE USED AS NEEDED TO MEET GRADE.

1. MINIMUM EDGE DISTANCE FOR AN OPENING ON THE OUTSIDE WALL SHALL BE NO LESS THAN 1'-0".

1. CLEAN AND LIGHTLY LUBRICATE ALL OF THE PIPE TO BE INSERTED INTO SUBSURFACE INFILTRATION SYSTEM. 2. IF PIPE IS CUT, CARE SHOULD BE TAKEN TO ALLOW NO SHARP EDGES. BEVEL AND LUBRICATE LEAD END OF PIPE. 3. ALIGN CENTER OF PIPE TO CORRECT ELEVATION AND INSERT INTO OPENING.



2. PANELS SHALL BE INSTALLED IN A TILT UP FASHION DIRECTLY ADJACENT TO OPEN END OF MODULE

3. CONNECTION HOOKS WILL BE SUPPLIED BY VENDOR WITH END PANELS TO SECURELY CONNECT PANEL TO ADJACENT MODULE (SEE PANEL CONNECTION ELEVATION VIEW).

4. ONCE CONNECTION HOOKS ARE ATTACHED, LIFTING CLUTCHES MAY BE REMOVED.


5. JOINT WRAP SHALL BE PLACED AROUND PERIMETER JOINT PANEL (SEE DETAILS HEREON).

	ZONE CHART				
ZONES	ZONE DESCRIPTIONS	REMARKS			
ZONE 1	FOUNDATION AGGREGATE	3/4" CRUSHED ROCK			
ZONE 2	BACKFILL	STRUCTURE BACKFILL IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS			
ZONE 3	FINAL COVER OVERTOP	MATERIALS NOT TO EXCEED 120 PCF			

STRUCTURAL DESIGN LOADING CRITERIA

LIVE LOADING:	AASHTO HS-20 HIGHWAY LOADING
GROUNDWATER TABLE:	HISTORICALLY 50' – 60' BELOW GROUND SURFACE
SOIL BEARING PRESSURE:	4500 PCF
SOIL DENSITY:	120 PCF
EQUIVALENT UNSATURATED LATERAL ACTIVE EARTH PRESSURE:	35 PSF/FT.
EQUIVALENT SATURATED LATERAL ACTIVE EARTH PRESSURE:	NA
APPLICABLE CODES	AASHTO ACI-318
BACKFILL TYPE:	SEE ZONE CHART HEREON

MATERIAL LIST						
COUNT	UNIT TYPE	DESCRIPTION				
401	I	7'-6" SINGLE TRAP				
58		7'-6" SINGLE TRAP				
2	IV	7'-6" SINGLE TRAP				
3	SPIV	7'-6" SINGLE TRAP				
5	PANEL	6" THICK PANEL				
80	JOINT TAPE	JOINT TAPE (14.5' PER ROLL)				
84	JOINT WRAP	JOINT WRAP (150' PER ROLL)				
5		MANHOLE STRUCTURE AND COVER				




UNDERGROUND SERVICE ALERT			REVISIONS		PREPARED BY:
CALL: TOLL FREE	REV. DATE	BY	DESCRIPTION	APP'V'D	
811					U
TWO WORKING DAYS BEFORE YOU DIG					

SUBSURFACE STORAGE SYSTEM INFORMATION: WATER STORAGE PROVIDED: 403,835 CUBIC FEET UNIT HEADROOM: 7'-6" SINGLETRAP UNIT QUANTITY: 464 TOTAL PIECES

DESIGN LOADING						
FILL DEPTH	TRACK WIDTH	MAX VEHICLE WEIGHT (KIPS)	MAX GROUND PRESSURE			
12"	12"	51.8	1690 psf			
	18"	56.1	1219 psf			
	24"	68.1	1111 psf			
	30"	76.7	1000 psf			
	36"	85.0	924 psf			

TYPICAL CONCRETE SUBSURFACE INFILTRATION SYSTEM SECTION NOT TO SCALE



ZONE CONSTRUCTION PROCEDURES

- 1. THE FILL PLACED AROUND THE STORAGE MODULES SHALL BE DEPOSITED CONCURRENTLY ON BOTH SIDES AND TO THE SAME ELEVATION. AT NO TIME SHALL THE FILL BEHIND ONE SIDE WALL BE MORE THAN 2' HIGHER THAN THE FILL ON THE OPPOSITE SIDE. BACKFILL SHALL EITHER BE COMPACTED AND/OR VIBRATED TO ENSURE THAT BACKFILL MATERIAL IS WELL SEATED AND PROPERLY INTER LOCKED. CARE SHALL BE TAKEN TO PREVENT ANY WEDGING ACTION AGAINST THE STRUCTURE. CARE SHALL BE TAKEN AS NOT TO DISRUPT THE JOINT WRAP FROM THE JOINT DURING THE BACKFILL PROCESS. THE PLACEMENT OF BACKFILL MATERIAL SHALL MEET THE REQUIREMENTS OF SECTION 300-3.5 OF THE GREENBOOK.
- 2. DURING PLACEMENT OF MATERIAL OVERTOP THE SYSTEM, AT NO TIME SHALL MACHINERY BE USED OVERTOP THAT EXCEEDS THE DESIGN LIMITATIONS OF THE SYSTEM. WHEN PLACEMENT OF MATERIAL OVERTOP, MATERIAL SHALL BE PLACED SUCH THAT THE DIRECTION OF PLACEMENT IS PARALLEL WITH THE OVERALL LONGITUDINAL DIRECTION OF THE SYSTEM WHENEVER POSSIBLE.
- 3. THE FILL PLACED OVERTOP THE SYSTEM SHALL BE PLACED AT 6" LIFTS. AT NO TIME SHALL MACHINERY OR VEHICLES GREATER THAN THE DESIGN HS-20 LOADING CRITERIA TRAVEL OVERTOP THE SYSTEM WITHOUT THE MINIMUM DESIGN COVERAGE. IF TRAVEL IS NECESSARY OVERTOP THE SYSTEM PRIOR TO ACHIEVING THE MINIMUM DESIGN COVER, IT MAY BE NECESSARY TO REDUCE THE ULTIMATE LOAD/BURDEN OF THE OPERATING MACHINERY SO AS TO NOT EXCEED THE DESIGN CAPACITY OF THE SYSTEM. IN SOME CASES, IN ORDER TO ACHIEVE REQUIRED COMPACTION, HAND COMPACTION MAY BE NECESSARY IN ORDER NOT TO EXCEED THE ALLOTTED DESIGN LOADING. SEE CHART FOR TRACKED VEHICLE WIDTH AND ALLOWABLE MAXIMUM PRESSURE PER TRACK.

SITE SPECIFIC DESIGN CRITERIA


4. STORAGE UNITS SHALL BE MANUFACTURED AND INSTALLED ACCORDING TO SHOP DRAWINGS, STAMPED BY A CALIFORNIA STRUCTURAL ENGINEER, SUBMITTED BY THE CONTRACTOR, AND APPROVED BY THE ENGINEER OF RECORD. THE SHOP DRAWINGS SHALL INDICATE SIZE AND LOCATION OF ROOF OPENINGS AND INLET/ OUTLET PIPE TYPES, SIZES, INVERT ELEVATIONS, AND SIZE OF OPENINGS.

FOR REFERENCE ONLY

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

DWG No. C-14 SHEET NO. 15 OF 46

SUBSURFACE INFILTRATION SYSTEM SECTION




TWO WORKING DAYS BEFORE YOU DIG

VE	1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com	× Exp. 9/30/2022 ★				Matthew Baumgardner, DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
			DRAWN BY:	TT	APR 2021	ha a de	
		OF CALIFORN	DESIGNED BY:	КН	APR 2021	1/24/11	
			CHECKED BY:	VB	APR 2021	Manuel Fabian, Civil Engineer Assistant II DATE	

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD


DETAILS

DWG No. C-16 SHEET NO. 17 OF 46



TWO WORKING DAYS BEFORE YOU DIG

MATERIAL LIST					
ITEM	COUNT	DESCRIPTION			
1	1	72IN MANHOLE BASE			
2	1	CHANNEL CONCRETE BASE			
3	1	72IN MANHOLE FLAT TOP			
4	3	72IN MANHOLE BARREL			
5	15	LADDER STEP RUNG POLYMER MH ASTM-C-478			
6	1	36IN DIA CAST IRON COVER			
7	1	36IN DIA CAST IRON FRAME			
8	1	GRADE RING 36IN DIA			
9	1	MOUNTING BRACKET FOR FLO-DAR SENSOR			
10	1	FLO-DAR AV SENSOR BY HACH W/SURCHARGE VELOCITY SENSOR OR AGENCY APPROVED EQUAL			



ISOMETRIC VIEW

MATERIAL LIST					
ITEM	COUNT	DESCRIPTION			
1	1	60IN MANHOLE BASE			
2	1	60IN MANHOLE FLAT TOP			
3	2	60IN MANHOLE BARREL			
4	1	36IN DIA CAST IRON COVER			
5	1	36IN DIA CAST IRON FRAME			
6	2	GRADE RING 36IN DIA			
7	10	LADDER STEP RUNG POLYMER MH ASTM-C-478			
8	1	FLO-DAR AV SENSOR BY HACH W/SURCHARGE VELOCITY SENSOR OR AGENCY APPROVED EQUAL			
9	1	MOUNTING BRACKET FOR FLO-DAR SENSOR			
10	1	CHANNEL CONCRETE BASE			

NOTE

ELECTRIC COMPONENTS IN VAULTS SHALL BE RATED FOR FULL SUBMERSION


GENERAL NOTES:

- 1. PLAN VIEW TOP SLAB WITH FRAMES AND COVERS ARE NOT SHOWN FOR CLARITY 2. ALL PRECAST CONCRETE COMPONENTS TO BE
- MANUFACTURED IN AN NPCA CERTIFIED PLANT
- 3. INLET/OUTLET PIPE STUBS PROVIDED BY CONTRACTOR

CONSTRUCTION NOTES:

- 1. CONTRACTOR TO VERIFY ALL DIMENSIONS AND
- ELEVATIONS IN FIELD PRIOR TO INSTALLATION. 2. PRECAST CONCRETE JOINTS TO BE SEALED
- USING BUTYL RUBBER COMPOUND 3. CONTRACTOR TO ADJUST ELEVATION OF FRAME
- AND COVER IN FIELD AS NECESSARY.
- 4. ALL MATERIALS AND MANUFACTURING METHODS SHALL CONFORM TO ALL APPLICABLE AND CURRENT ASTM, AASHTO, AND NPCA STANDARDS AND SPECIFICATIONS. 5. CONTROL PANEL LOCATION SHOWN ON







CHECKED BY:

GLENOAKS BLVD

PROFILE VIEW

SCALE: 1"= 4'

Molen

Matthew Baumgardner,

Director of Public Works

APR 2021 Manuel Fabian, Civil Engineer Assistant II DATE

DETAIL 2: FLOW METER AND VAULT



1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com

× Exp. 9/30/2022 ★ CIVIL CIVIL CALIFORNIA CALIFORNIA CIVIL CALIFORNIA COF CALIFORNIA COF CALIFORNIA CIVIL	۷. ۱	
★ Exp. <u>9/30/2022</u> ★		
	A REDUCE	No.85752 No.85752 Att_flue Exp. <u>9/30/2022</u> ★

APR 202 DRAWN BY: DESIGNED BY: APR 202 KH

VB

		2	2
		3	1
		5	1
		6	1
		7	1
PLAN VIEW		8	2
6 (7)		10	15
		11	2
PROFILE VIEW SCALE: 1"= 4"	A		1 – Ø3" HOLE ELECT
			COI
		±20)'-0"
MAGE AND COVER LADDER STEPS PLAN VIEW			Y
		6" THICH CRUSHE	< OF ¾" ⊡ ROCK

ITEM COUNT

2

NOTE:


ELECTRIC COMPONENTS IN VAULTS SHALL BE RATED FOR FULL SUBMERSION


SEQUENCE OF OPERATIONS:

- WILL BE CLOSED.

GENERAL NOTES:

- CONSTRUCTION NOTES:
- 1. CONTRACTOR TO VERIFY ALL DIMENSIONS AND ELEVATIONS IN FIELD PRIOR TO INSTALLATION.
- 2. PRECAST CONCRETE JOINTS TO BE SEALED USING BUTYL RUBBER COMPOUND.
- 3. CONTRACTOR TO ADJUST ELEVATION OF FRAME AND COVER IN FIELD AS NECESSARY.
- 4. ALL MATERIALS AND MANUFACTURING METHODS SHALL CONFORM TO ALL APPLICABLE AND CURRENT ASTM, AASHTO, AND NPCA STANDARDS AND SPECIFICATIONS. 5. CONTROL PANEL LOCATION SHOWN ON ELECTRICAL PLANS.





Ø36" CAST IRON


 $\pm 20' - 4'$


6" THICK OF 34"


CRUSHED ROCK

FRAME AND COVER

-LADDER STEPS








MATERIAL LIST
DESCRIPTION
ELECTRICALLY ACTUATED KNIFE GATE VALVE 36IN
PIPE 16IN FLG X PE DUCTILE IRON SPOOL 3FT
84IN MANHOLE BASE
84IN MANHOLE FLAT TOP
CI RING 48X5 A–1428 (NOT CALLED OUT IN DETAIL
CI CVR 48X5 MAIN A-1428
CI CVR 48X5 VIEW A-1428
84IN MANHOLE BARREL
GRADE RING 48DIA X 12IN
LADDER STEP RUNG POLYMER MH ASTM-C-478 9-3/16 X 13IN PS2-PF-DF
CRADLE PIPE SUPPORT 30 ADJ TRIPAC TP100

MATERIAL LIST

ITEM	COUNT	DESCRIPTION
1	1	60IN MANHOLE BASE
2	3	60IN MANHOLE BARREL
3	1	60IN MANHOLE FLAT TOP
4	1	ELECTRICALLY ACTUATED KNIFE GATE VALVE 18IN
5	2	18IN DIP FLG X PE SPOOL
6	1	36IN DIA CAST IRON FRAME
7	1	36IN DIA CAST IRON COVER
8	2	GRADE RING 36IN DIA
9	2	PIPE SUPPORT
10	2	CONNECTOR BOOT S206-24A CORE-SEAL ASTM C923/C1644 HOLE-24 18.00-19.50



1. THE GATE VALVES LOCATED AT THE FIRST STREET AND GLENOAKS BOULEVARD DIVERSIONS WILL NORMALLY BE IN AN OPEN POSITION.

2. ONCE THE LEVEL IN THE TANK REACHES 7 FEET (ELEVATION: 1039.0 FEET), THE GATE VALVE LOCATED AT THE GLENOAKS BOULEVARD DIVERSION

3. ONCE THE LEVEL IN THE TANK REACHES 7.3 FEET (ELEVATION: 1039.3 FEET), THE GATE VALVE LOCATED AT THE FIRST STREET DIVERSION WILL BE CLOSED. 4. BOTH VALVES WILL REOPEN ONCE THE LEVEL IN THE TANK IS EQUAL OR LESS THAN 6 FEET DEEP (ELEVATION: 1038.0 FEET).

- 1. PLAN VIEW TOP SLAB WITH FRAMES AND COVERS ARE NOT SHOWN FOR CLARITY
- 2. ALL PRECAST CONCRETE COMPONENTS TO BE MANUFACTURED IN AN NPCA CERTIFIED PLANT
- 3. INLET/OUTLET PIPE STUBS PROVIDED BY CONTRACTOR


DETAIL 3: GATE VALVE AND VAULT

OC N	SAN OR		
and a	SAN F	⁻ E	RNANDO
	HISTORIC	&	VISIONARY

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

DETAILS

DWG No. C-17 SHEET NO. 18 OF 46




DRAWN BY: TT DESIGNED BY: KH CHECKED BY: VB

APR 2021


APR 2021

papp


APR 2021 Manuel Fabian, Civil Engineer Assistant II DATE





UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED BY:
CALL: TOLL FREE 811	REV.	DATE	BY	DESCRIPTION APP'V'D	C
TWO WORKING DAYS BEFORE YOU DIG					-




AV VY








★ Exp. 9/30/2022 ★				Matthew Baumgardner, DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
CIVIL ONT	DRAWN BY:	TT	APR 2021	12 a d	
E OF CALIFORN	DESIGNED BY:	КН	APR 2021	1 mar mar	
	CHECKED BY:	VB	APR 2021	Manuel Fabian, Civil Engineer Assistant II DATE	






811		
011		



DWY DWY		ď	E DWY		DWY DWY
56) 611			30.0'		
29+00 N 48°52'24" E	19.0'	30+00		 (31+00 JESSI
12.5'	19.0'		MHS®	Ψ	
	4.0' <u>30.0'</u>		30.0'		
51 DWY	(51) ° FH	ିତ	DWY		



					G	ENERAL	_ N	OTES				
	THIS DRAWING CONTAINS STAND THIS PROJECT.	ARD SYMBOL	S. NOT AL	L SYMBO	DLS SHOWN A	RE USED ON	9.	ALL ABOVE GROUND CONDUIT SHALL BE U	JSED FO	R SHOR	T CONNE	CTIONS TO LI
	THESE DRAWINGS ARE SUPPLEN OF THE SPECIFICATIONS FROM) SPECIF	ICATIONS. OF	STAIN A COPY	10	VIBRATING EQUIPMEN WHERE EXPOSED TO	WEATHER	२.		
	CONTRACTOR <u>SHALL NOT</u> CUT A THAT WOULD IMPAIR THEIR STR		RAL MEMB	BER(S) OI	R USE ANY A	TTACHMENTS	10.	ALL CONDUCTORS SH STRANDED AND NO. THNN/THWN/THW.				
	CONTRACTOR SHALL DESIGN TH MEMBER(S) AND SUBMIT THE D					SUPPORT	11.	OUTLET BOXES SHALI AND PROPER DEVICE CAST BOX.				
	THE ENTIRE INSTALLATION SHAL ELECTRICAL CODE, FEDERAL CO REGULATIONS, AND ALL OTHER	MMUNICATION	COMMISIC	ON (FCC)	, STATE FIRE	MARSHALL	12.	ALL SURFACE-MOUNT SECURED TO WALL O			EQUIPME	NT AND DEVI
	THE CONTRACTOR SHALL OBTAIL	SE.					13.	TEST THE ENTIRE SY SPECIAL SYSTEMS AR	E COMPI	LETE AN	ID FUNCT	ION PROPERL
	REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL						13.	CORRECTIONS AND LI PROVIDE SEPARATE G				
	INSTALLATION, CONSTRUCTION T PROPERLY-OPERATING SYSTEM, DRAWINGS, AS SPECIFIED HEREI	ENERGIZED	THROUGHC	OUT AND	AS INDICATED		14.	ALL OUTDOOR EQUIP ENCLOSURE EXCEPT ALL KEYED ALIKE WIT	AS NOTE	D. ALI	_ EQUIPM	ENT AND DEV
	ALL MATERIALS AND EQUIPMENT CONDITION WHEN INSTALLED AN MANUFACTURER THROUGHOUT F	D SHALL BE OR EACH CL	OF THE E	BEST GRA	ADE AND OF EQUIPMENT.	THE SAME MATERIALS	15.	ACCEPTANCE. LIGHT OR SCREENED EXISTING TO REMAIN				
	SHALL BE LISTED AND APPROVI INSPECTION LABEL UL WHERE S WITH THE APPROVAL OF THE D BODIES HAVING JURISDICTION.	SUBJECT TO IVISION OF IN MATERIALS S	SUCH APF NDUSTRIAL SHALL BE	PROVAL. SAFETY MANUFAC	MATERIALS S AND ALL GOV TURED IN AC	HALL MEET /ERNING	16.	ARE NEW TO BE PRO	OVIDED, I	NSTALLI	ED, TESTE	ED, COMMISSIO
	WITH APPLICABLE STANDARDS E	STABLISHED	BY ANSI,	NEMA, AN	ND NBFU.							
		STRU	MEN	ITAT	TON, (CONTRC)L	FUNCTION	N SY	/ME	BOL	5 & DE
(x		IT/FIELD MOU XX OR XXXX			8		— E	ELECTRICAL SIGNAL	_	0-0-	-0-0-	_ COMMUNI LOGIC SI
		NTS SHARING IT/FIELD MOU		ON HOUS	SING,	# # #	F	PNEUMATIC SIGNAL	-	-v-	∽–∾–	- RADIO OF SIGNAL
	PANEL MOUNTED	, OUNTED, OPE IN LCP, UOI	RATOR AC			\bigcirc	E	MICROPROCESSOR BASED LOCAL DPERATOR INTERFACE				
							(MMI) MICROPROCESSOR			<u>NSDUC</u> = analo	
	\bigcirc	OUNTED, OPE					E (BASED REMOTE (SCADA DPERATOR INTERFACE)		= DIGITA	
(IN LCP, UO					``	(MMI) PLC INPUT/OUTPUT PO	INT.	E	= VOLTA	AGE
	PLC SHAF	RED DISPLAY/	CONTROL	FUNCTIO	NS		[DISCRETE NPUT SHOWN	,	F	= FREQI	UENCY
		ISA	_ S	5.1	TABLE	1				Н	= HYDR/	AULIC
			TIFICA	- • •	LETTE	RS				<u>PLC</u>	DEFI	<u>NITIONS</u>
	FIRST LETTER(S) EASURED OR INITIATING VARIABLE	MODIFIEF	2		OR PASSIVE	SUCCEEDING LETTER		MODIFIER		AI	= AN/	ALOG INPUT
-	A ANALYSIS B BURNER , COMBUSTION				LARM					AO	= AN	ALOG OUTPU
(C CONDUCTIVITY D DENSITY	DIFFERENT		С	CLOSE	CONTROL		CLOSED		DI	= DIS	SCRETE INPU
E	VOLTAGE F FLOW RATE	RATIO (FRAC		PRIMAR	Y ELEMENT					DO	= DIS	SCRETE OUTF
	G GAUGE H HAND (MANUAL)			GLASS, VI	EWING DEVICE			HIGH				
,	I CURRENT (ELECTRICAL) J POWER	SCAN		INI	DICATE				<u>Se</u>	LF	CON	ITAINE[
ł	<pre> TIME, TIME SCHED. LEVEL </pre>	TIME RATE CHANGE		1	light	CONTROL STATIO	ON	LOW	EQ	UIP	MEN	t tag
	M MOISTURE	MOMENTA	RY I					MIDDLE				
(D TORQUE D PRESSURE, VACUUM				OPEN CONNECTION			OPENED			D-X	
-	Q QUANTITY	INTEGRAT TOTALIZE			CONNECTION					(ARV	= AIR RELI
	R RADIATION S SPEED, FREQUENCY	SAFETY		RECORD	OR PRINT	SWITCH			5		ARV ASV ARVR	= AIR REL = ANTI-SIF = AIR AND
	T TEMPERATURE J MULTIVARIABLE			MULTI	FUNCTION	TRANSMIT MULTIFUNCTION		MULTIFUNCTION	D:		E FCV	= EDUCTOR = FLOW CO
	V VIBRATION W WEIGHT, FORCE				WELL	VALVE, LOUVER					G LCV	= GATE = LEVEL C
	X UNCLASSIFIED Y EVENT, STATE OR PRESENCE	X AXIS Y AXIS		UNCL	ASSIFIED	UNCLASSIFIED RELAY, COMPUT	ΓE,	UNCLASSIFIED		\langle	M P PCV	= MECHANI = PUMP = PRESSU
	Z POSITION	Z AXIS				SOLENOID, CONV DRIVER, ACTUATOR, CONTROL ELEME	FINA	- NTS			PRV PSE	= PRESSUR = RUPTUR
	REFERENCE ISA-S5.1 SECTION	5.1 AND TABLE	E 2 FOR E	XPLANATIO	N AND TYPICAL	•		·			PSV T	= PRESSU = TANK
ICE	TO CONTRACTOR:]						TCV SP SOL	= TEMPERA = SUMP P = SOLENOI
ALL THE	BE THE SOLE RESPONSIBILI	TY OF THE		TOR TO						Ĺ	JUL	JULLINU
SEV	USA UNDERGROUND ALERT DUND UTILITIES NO LESS TI 'EN DAYS PRIOR TO CONSTR		איז אטו	∖ MUKE					X:	UNI	t numbe	ER
CONT GE D	RACTOR SHALL ASSUME SOL DONE TO EXISTING UTILITIES CONCRETE/LANDSCAPING D	E RESPONS OR STREET URING CON	IBILITY FO IMPROVE	OR ANY MENTS N.								
	RGROUND SERVICE ALE		2		1	REVISIO	NS)			PREP	ARED BY:
JEFOF			EV. DATE	BY			RIPTIC			APP'V'[5	
	CALL: TOLL FF											
		F										
	VORKING DAYS BEFORE YOU											

	PLANS	ELECT
RIGID STEEL CONDUIT. FLEXIBLE	$\overline{+}$	125V, 20A RECEPTACL
TO LIGHTING FIXTURES AND OTHER EXIBLE CONDUIT AND FITTINGS	÷	125V, 20A
D VOLTS. LARGER SHALL BE		RECEPTACL
ID UNLESS USE TYPE		WEATHERPF
ED HUBS, GASKETED COVER PLATES,		SAME AS E
TCH EXISTING BOXES IF OTHER THAN	S	WALL SWIT
DEVICES SHALL BE PROPERLY		
HE ELECTRICAL COMPONENTS AND OPERLY. MAKE NECESSARY ATION.		
D FLEX CONDUITS.		
OF NEMA 4X STAINLESS STEEL		
D DEVICES SHALL BE PAD LOCKED	-①	THERMOSTA
		JUNCTION
OR NON-ELECTRICAL COMPONENTS. UNLESS OTHERWISE. HEAVY LINE MISSIONED AND READY FOR USE.	•	CONTROL S
DSED PER STATE REGULATIONS.		SEE SCHEN
	E-	FUSED SWI
		ENCLOSED
DEFINITIONS	⊠-2	NEMA SIZE
IMUNICATION OR	⊠	GROUND W
IC SIGNAL	\otimes	GROUND R BURIAL DEI
IO OR TELEMETRY NAL	(XXX)	CONDUIT D
		CONDUIT IN 1" MIN.
		CONDUIT A
I = CURRENT		NOTES OF REQUIREME
P = PNEUMATIC		
PF = PULSE FREQUENCY	G †	EXOTHERMI
PD = PULSE DURATION	o	CONDUIT B
R = RESISTANCE	•	CONDUIT B EQUIPMENT
		CONDUIT S
<u>NS</u>		FLEXIBLE C
IPUT		MOTOR CO
UTPUT		PANELBOAR
INPUT		FLOURESCE SEE FIXTUF
OUTPUT		WALL MOUI
		POLE MOUI
		CELLULAR
NED VALVE &	<u> </u>	JUNCTION
AG NUMBERS	۲	GENERATOR SEE PLANS
		TWIST LOCI SEE PLANS
RELEASE VALVE I–SIPHON VALVE AND VACUUM RELEASE VALVE		NEUTRAI
ICTOR W CONTROL VALVE E		CROSS LIN #12 AWG U
E EL CONTROL VALVE CHANICAL EQUIPMENT		GROUND C INDICATE 2
SSURE CONTROL VALVE		
TURE DISK SSURE RELIEF VALVE		GROUND A
K PERATURE CONTROL VALVE		GND., UNLI
IP PUMP ENOID VALVE	THESE PLANS WERE P	
	AVAILABLE RECORDS AN OF SUBSTRUCTURES AN	
	THE CONTRACTOR, IN A TO LOCATE AND PROTE	

\ominus	125V, 20A NEMA 5-20R SIMPLEX	NORMALLY	NORMALLY	DEVICE
÷	RECEPTACLE, UON 125V, 20A NEMA 5–20R DUPLEX		CLOSE	CONTACT
	RECEPTACLE, UON SAME AS DUPLEX RECEPTACLE ABOVE EXCEPT		0_0	TIMED CONTACT CONTACT ACTION RETARDED ON
-	WEATHERPROOF, GFCI SAME AS DUPLEX RECEPTACLE ABOVE EXCEPT GFCI	\sim		ENERGIZATION TIMED CONTACT
S	WALL SWITCH MOUNT AT +45" AFF, UON 2-DOUBLE POLE	\rightarrow	o ↓ o	CONTACT ACTION RETARDED ON DE-ENERGIZATION
	3–THREE WAY 4–FOUR WAY			PUSH BUTTON SINGLE CIRCIUIT MOMENTARY CONTACT PUSH BUTTON SINGLE CIRCIUIT
	b-OUTLET CONTROLLED			LOCK-OUT
	CRE-CORROSION RESISTANT D-DIMMER	<i>∞</i> °	070	LIMIT SWITCH
	EP-EXPLOSION PROOF K-KEY OPERATED		o To	LIQUID LEVEL SWITCH
	P-PILOT LIGHT WP-WEATHERPROOF		To	PRESSURE OR VACUUM SWITCH
	T-TIMER SWITCH	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	To	FLOW SWITCH
-①	THERMOSTAT OUTLET, MOUNT AT +66" UON			TEMPERATURE SWITCH
J	JUNCTION BOX, SIZED AS REQUIRED			SELECTOR SWITCH
•	SEE SCHEMATIC DIAGRAM		<u>-</u>	MANUAL MOTOR STARTER
	NON-FUSED SWITCH, 30A, 3P, UON	0/	 ′L's /f	MOTOR OVERLOAD HEATER COM
F	FUSED SWITCH, 30A, 3P, UON		х <u>—</u>	MOTOR OVERLOAD HEATER
⊠_2	ENCLOSED COMBINATION STARTER, NUMBER INDICATES NEMA SIZE, NEMA SIZE #1 UON	χ	A)	PILOT LIGHT R=RED, W=WHITE, G=GREEN, /
\boxtimes	GROUND WELL, CONCRETE WITH LABELED COVER	Q 0	A	PILOT LIGHT, PUSH TO TEST R=RED, W=WHITE, G=GREEN, /
⊗	GROUND ROD, 5/8" DIA. X 10' COPPER CLAD STEEL. BURIAL DEPTH PER OWNER'S INSTRUCTIONS		R R	CONTROL RELAY, FUNCTION AS
(XXX)	CONDUIT DESIGNATION SEE CONDUIT SCHEDULE CONDUIT IN SLAB OR UNDER GROUND,		D	TIME DELAY RELAY
	1" MIN. CONDUIT ABOVE GRADE, 3/4" MIN. SEE GENERAL	(F	\sim	PHOTO CELL
	NOTES OF THIS SHEET FOR ADDITIONAL REQUIREMENTS.		sc	STARTER COIL
P	CONDUIT INTERSECT WITH CONDULET	⁄ــه	∕~∘	SOLENOID OPERATED VALVE
G +	EXOTHERMIC WELD CONNECTION		\mathcal{Y}	PHASE MOTOR
O	CONDUIT BENDS TOWARD OBSERVER OR EQUIPMENT		þ	BELL OR BUZZER
•	CONDUIT BENDS AWAY FROM OBSERVER OR EQUIPMENT	Ē	ТМ	ELAPSED TIME METER
]	CONDUIT STB-OUT AND CAPPED		P	FUSE, TRIP RATING AS NOTED
	FLEXIBLE CONDUIT CONNECTION		<u><u></u></u>	CONTROL POWER TRANSFORME
\mathcal{N}	MOTOR CONNECTION	ין 		GROUND
	PANELBOARD			WIRING IN MOTOR STARTER
	FLOURESCENT FIXTURE SEE FIXTURE SCHEDULE			FIELD WIRING
	WALL MOUNTED FIXTURE SEE FIXTURE SCHEDULE		□ 	TERMINAL BLOCK
-X OR •-	POLE MOUNTED LIGHT			BATTERY
	CELLULAR ANTENNA		10A	CIRCUIT BREAKER, TRIP RATING
- <u></u>	JUNCTION BOX / PULLBOX GENERATOR RECEPTACLES	€ ●		POWER MONITORING DEVICE
	SEE PLANS FOR RATINGS. TWIST LOCK RECEPTACLE, WP	V	FD	VARIABLE FREQUENCY DRIVE
 <u>+ (</u>	SEE PLANS FOR RATINGS	~	m	DC CHOKE / LINE REACTOR
	CONDUIT RUN (GROUND CONDUCTOR	₽	-M 	SERVICE METER
	NEUTRAL CONDUCTOR		H	BLOCK HEATER / SPACE HEAT
	CROSS LINES INDICATE NUMBER OF CONDUCTORS, #12 AWG UNLESS OTHERWISE INDICATED, SIZE	s	SS	SOLID STATE STARTER
	GROUND CONDUCTOR PER N.E.C., NO CROSS LINES INDICATE 2#12 & 1#12 GND	30A	NEMA 1 	COMBINATION STARTER WITH M PROTECTION, NEMA SIZE MOTO OVERLOAD HEATERS
	MINIMUM CONDUIT RUN AS SHOWN IS 3/4"C ABOVE	۵۰۰۰۰ ۵۵		STEP DOWN TRANSFORMER WIT



1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com

	PROFESSIONA	
/&	N. FERNAN	C
		13
10	No. E 012496 [°]	1A
E E	EXP. 9/30/21	<u> </u> 2
_ \\★_	04/22/21	/★//
<u>\</u> \}	ECTRICA	S/
N.	E OF CALLEON	
	· 0/1E	

				a
CONSULT 15 Flagstone,	ING Trabuco 700	Canyon, CA 92679 F:(206) 203-1316 www.linkture.com	Matthew Baumgardner DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
DRAWN BY:	JA	APRIL 2021	12/11	
DESIGNED BY:	JA	APRIL 2021	1. 4 /11	
CHECKED BY:	OF	APRIL 2021	Manuel Fabian, Civil Engineer Assistant II DATE	

NElem				
atthew Baumgardner rector of Public Wor			DATE	
. NO.: <u>71932</u>	EXP.	DATE:	<u>12/31/2021</u>	
/pl/				



AM SYMBOLS		ABBREVI	ATIO	NS
	A A/C, AC AFF	AMPERE, AUTO, AUTOMATIC ALTERNATING CURRENT ABOVE FINISHED FLOOR	NA N/C, NC NEC	INTRUSION ALARM NORMALLY CLOSED NATIONAL ELECTRICAL CODE
	AFF AI AIC	ABOVE FINISHED FLOOR ANALOG INPUT TO PLC AVAILABLE INTERRUPTING CURRENT	NEC	NATIONAL ELECTRICAL CODE NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
N RETARDED ON	AIC ANN AO	AVAILABLE INTERRUPTING CURRENT ANNUNCIATOR ANALOG OUTPUT FROM PLC	NIC N/O, NO	ASSOCIATION NOT IN CONTRACT NORMALLY OPEN
	ATS AUX	AUTOMATIC TRANSFER SWITCH AUXILIARY	NO., # NS	NUMBER INTRUSION SWITCH
N RETARDED ON DN	AWG	AMERICAN WIRE GUAGE	NTS	NOT TO SCALE
SINGLE CIRCIUIT NTACT	BLDG. BRKR	BUILDING BREAKER	OC	ON CENTER
SINGLE CIRCIUIT	BTCW	BARE TINNED COPPER WIRE	P PAH	POLE PRESSURE ALARM HIGH
	C CAB	CONDUIT CABINET	PAL P&ID	PRESSURE ALARM LOW PIPING AND INSTRUMENTATION DIAGRAM
VITCH	C/B, CB CKT	CIRCUIT BREAKER CIRCUIT	PB PC	PULL BOX PHOTO CELL
ACUUM SWITCH	CLG CNTRL CO	CEILING CONTROL CONDUIT ONLY, WITH PULL ROPE	PFA PFR	POWER FAILURE ALARM PHASE FAILURE RELAY
	COMM COMM CPT	COMMUNICATION CONTROL POWER TRANSFORMER,	PH, Ø PID	PHASE PROPORTIONAL, INTEGRAL,
WITCH	CPU	120V SECONDARY, UON CENTRAL PROCESSING UNIT	PLC	AND DERIVATIVE (TUNING) PROGRAMMABLE LOGIC CONTROLLER
Н	CM	COMMUNICATION MODULE	P/L PM PNL	PROPERTY LINE POWER MONITORING PANEL
	DC DI	DIRECT CURRENT DISCRETE INPUT TO PLC	PS PSH	PULL SECTION PRESSURE SWITCH HIGH
STARTER	DSW DO	DISCONNECT SWITCH DISCRETE OUTPUT FROM PLC	PSL PT	PRESSURE SWITCH LOW PRESSURE TRANSMITTER
D HEATER CONTACTS	D/P DPDT	DIFFERENTIAL PRESSURE DOUBLE-POLE, DOUBLE-THROW	PTT PVC	PUSH-TO-TEST POLYVINYL CHLORIDE
D HEATER	DPM DWG	DIGITAL PANEL METER DRAWING	(R)	RELOCATE-PROVIDE WIRING AND CONDUITS
E, G=GREEN, A=AMBER	EA EF-X	EACH	RE	AS NECESSARY REPLACE EXISTING
SH TO TEST	ELECT. EMI	EXHAUST FAN NO.X ELECTRICAL ELECTROMAGNETIC INTERFERENCE	REQ'D. REQMT.	REQUIRED REQUIREMENT
E, G=GREEN, A=AMBER	EQUIP	EQUIPMENT EXISTING TO REMAIN	RTU	REMOTE TERMINAL UNIT
FUNCTION AS DEFINED	EX, (E)	EXISTING	SHT SLD SPDT	SHEET SINGLE LINE DIAGRAM SINGLE-POLE DOUBLE-THROW
AY	FA F	FLOW ALARM FUSE	SPD1 SPEC SPST	SINGLE-POLE, DOUBLE-THROW SPECIFICATION SINGLE-POLE, SINGLE-THROW
	FM FS	FACTORY MUTUAL FLOW SWITCH OR FLOAT SWITCH	S/N	SOLID NEUTRAL START-STOP
	GEC	GROUND ELECTRODE CONDUCTOR	S/S SS SSS	START-STOP STAINLESS STEEL, SOFT STARTER SOLID-STATE STARTER
ATED VALVE	GFI, GFCI GFP	GROUND FAULT CIRCUIT INTERRUPTER GROUND FAULT PROTECTION	SW	SWITCH
	GND OR G	HAND-OFF-AUTOMATIC	TB TBD	TERMINAL BLOCK, OR TERMINAL BOX TO BE DISCUSS/DETERMINED
٦	HOA HP HT	HORSEPOWER HEIGHT	TD TERM	TIME DELAY TERMINAL
ÈTER	H HS	HEATER OR HAND SWITCH HAND SWITCH	TYP. TSP	TYPICAL TWISTED SHIELDED PAIR, 2/C#16 AWG
NG AS NOTED	1/0	INPUT/OUTPUT	STS	TWISTED SHIELDED TRIAD, 3/C#16 AWG
R TRANSFORMER	IC IN OR "	RMS SYM. INTERRUPTING CAPACITY RATING INCHES	UL UON	UNDERWRITER'S LABORATORY UNLESS OTHERWISE NOTED
	JB	JUNCTION BOX	UPS UG	UNINTERRUPTIBLE POWER SUPPLY UNDERGROUND
R STARTER	JS	POWER SWITCH	UGPS	UNDERGROUND PULL SECTION
	K KCMIL	THOUSAND THOUSAND CIRCULAR MILS	V VA VFD	VOLTAGE VOLT-AMPERES VARIABLE ERECUENCY DRIVE
к	KVA KVAR	KILOVOLT-AMPERE KILOVOLT-AMPERE REACTIVE	VFD XFMR	VARIABLE FREQUENCY DRIVE
·	KW LAH	KILOWATT LEVEL ALARM HIGH	XTMR	TRANSFORMER
	LAH LAL LCL	LEVEL ALARM HIGH LEVEL ALARM LOW LONG CONTINUOUS LOAD	W WH	WATT WATTHOUR
R, TRIP RATING AS NOTED	LCP	LOCAL CONTROL PANEL LARGEST MOTOR	WP WT	WEATHERPROOF WATER TIGHT
ING DEVICE	LOS LSH	LOCK OUT SWITCH LEVEL SWITCH HIGH	Z	IMPEDANCE
ENCY DRIVE	LSL LT	LEVEL SWITCH LOW LEVEL TRANSMITTER	ZSC ZSO	LIMIT SWITCH CLOSED LIMIT SWITCH OPEN
	LTG LV	LIGHTING LOW VOLTAGE	3W 4W	
NE REACTOR			4W	FOUR-WIRE
	MA MAX MCC	MANUAL OR MILLIAMPERE MAXIMUM MOTOR CONTROL CENTER		
/ SPACE HEATER	MCP MFR	MOTOR CONTROL CENTER MOTOR CIRCUIT PROTECTOR MANUFACTURER		
ARTER	MH MN	MANUTACTORER MANHOLE MINIMUM	NOTES:	
ARTER WITH MOTOR CIRCUIT	ML MLO	MAIN LUG MAIN LUG ONLY	DEVICES,	IIN LINES DEPICTING WIRES, EQUIPMENT, COMPONENTS, CONDUITS, ETC. ARE
MA SIZE MOTOR STARTER AND ERS	mm MOV	MILLIMETER MOTOR OPERATED VALVE		AND ARE SHOWN FOR CLARITY.
	MSB MTD	MAIN SWITCHBOARD MOUNTED	APPEAR	SYMBOLS AND ABBREVIATIONS ABOVE ON THE ACCOMPANYING CONTRACT OR ELSEWHERE IN THE CONTRACT
NSFORMER WITH SECONDARY	MTG MTS	MOUNTING MANUAL TRANSFER SWITCH	DOCUME	
	(N)	NEW, TO BE PROVIDED AND		
MADE A REASONABLE REVIEW OF	(NL)	INSTALLED BY THE CONTRACTOR NEW LOCATION OF RELOCATED DEVICE		
NG THE EXISTENCE AND LOCATION GIVEN HEREON.				
DUE PRECAUTIONARY MEASURES				

<u>San Fernando</u> HISTORIC & VISIONARY CITY OF SAN FERNANDO DEPARTMENT OF PUBLIC WORKS


DWG No. San Fernando Regional Park Infiltration Project E-01 SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD SHEET NO.

GENERAL NOTES, ELECTRICAL SYMBOLS, SCHEMATIC SYMBOLS, ABBREVIATIONS

24

OF

46



TWO WORKING DAYS BEFORE YOU DIG

ELECTRICAL DESIGN LOAD SUMMARY								
SERVICE DESCRIPTION	LOAD (kW)							
(E) PANEL LD	36.0							
(E) PANEL LF	36.0							
(E) OUTSIDE REST R. LITE	2.5							
(N) PANEL RH	19.2							
(E) PANEL B	14.4							
(E) PANEL LC	10.1							
(E) PANEL LB	7.2							
(E) PANEL LA	7.2							
(E) PANEL MSS	57.6							
SAFETY FACTOR (25% OF TOTAL LOAD)	47.6							
TOTAL KW	237.9							
TOTAL AMPERE AT 208V, 3PH	660.3							

SLD PLAN KEY NOTES:

- (1) PROVIDE (N) 100A, 3P, CIRCUIT BREAKER. FAULT RATING OF THE (N) BREAKER SHALL MATCH WITH THE (E) AVAILABLE FAULT RATING.
- (2) (E) LOADS. MATCH (E) PANEL RH BRANCH BREAKER SIZES. IF CABLES ÀRE NOT LONG ENOUGH SPLICE AND EXTEND AS NECESSARY. MATCH EXISTING CABLE SIZE.
- (3) TAP (N) GROUND WIRE TO (E) GROUNDING SYSTEM. FIELD VERIFY EXACT LOCATION OF GROUND ROD.

VOLTAGE DROP CALCULATION 3 PHASE, 3 OR 4 WIRE											
EQUIPMENT	WIRE LENGTH (FT)	LOAD (A)	VOLTS (V)	DESIRED % DROP	MIN. CIRC MILS	SELECTED WIRE	VOLTAGE DROP (V)	VOLTAGE AT TERM. (V)	%VD		
P05	552	80	208	2%	248698	250000	4.14	203.9	1.99%		
P06	237	48	203.9	3%	41561	52620	4.83	199.0	2.37%		
P01	14	24.2	199.0	3%	1268	16510	0.46	198.6	0.23%		
		-		DROP CAI 3 WIRE FR							
EQUIPMENT	EQUIPMENT LENGTH (A) (V) % DROP MILS WIRE DROP (V) AT T					VOLTAGE AT TERM. (V)	%VD				
P03	6	16	199	3%	415	6530	0.38	198.65	0.19%		

PROFESS/044 PROFESS/044 FERNAND No. E 012496 EXP. 9/30/21 ★ 04/22/21	LINKTUF CONSULTING 15 Flagstone, Trabuco P:(949) 317-4700 email@linkture.com	ENGINEERS Canyon, CA 92679 F:(206) 203-1316	Matthew Baumgardner DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
S. ELECTRICA M	DRAWN BY: JA	APRIL 2021	12 n di	
F OF ON IFOR	DESIGNED BY: JA	APRIL 2021	1 and the	
OF CALIT	CHECKED BY: OF	APRIL 2021	Manuel Fabian, Civil Engineer Assistant II DATE	



PROFESSIONAL FERNANDEL
Ko. E 012496 EXP. 9/30/21 ★ 04/22/21 ★
OF CALIFORNIE

•	1561	E.
	-	JLL EL
		ww



Γ								PA	NEL "F	RH1" S	CHEDU	JLE								
V		- FRA AGE: E:		SIZE	:		100A 120/208V 3PH, 4W	ENCLOS	EAKER SIZ URE: JPT ING RA		60A NEMA 1 10 kA		MOUNTING	s; ins	SIDE	CON	TROL	PAN	EL	
	(CKT I	BKR		QTY	(LC	DAD (WAT	TS)				QT	(CKT			1
	KT IO.	AMPS	POLES	LTG	REC	MISC	DESCRIPT ION	LOAD	L1	L2	L3	LOAD	DESCRIPTION	MISC	REC	LTG	POLES	S	CKT NO.	
	1	40	3				ELECT RIC ACT UAT OR	2906	4106			1200	CONT ROL PANEL				1	20	2	CI
Ļ	3							2906		2906			SPARE						4	
	5							2906			2906		SPARE						6	
	7						SPARE		0				SPARE						8	
	9						SPARE			0			SPARE						10	
	1						SPARE				0		SPARE						12	
							PHASE TOTALS (WATTS)	4106	2906	2906	NOTE/	/S:							
							PHASE BALANCE	12%	41%	29%	29%		CIRCUIT BREAKERS SHALL BE 80% RATEI	D.						
	TOTAL CONNECTED LOAD (WATTS)						9918			DENOTES CONTINUOUS LOAD - DENOTES LARGEST MOTOR LOAD										
			259	% OF	LO	NG	CONTINUOUS LOAD (LCL) AND LARGEST	MOTOR	2480				-DENOTES LANGEST MOTOR LOAD							
							TOTAL LOAD (12398										
							TOTAL LOAD	(AMPS)		29.8										j.

								PA	NEL "	RH" SC	CHEDU	LE								
	PANE VOLT PHAS	AGE:		SIZE	ł		100A 120/208V 3PH, 4W	ENCLOS	EAKER SIZ URE: IPT ING RA		100A NEMA 1 10 kA		MOUNTING:	SUF	RFAC	CE				
	CKT	T CKT BKR QTY				LC	DAD (WAT 1	(WATTS)		_		QT \ I	1	CKT BKR		СКТ				
	NO.	AMPS	POLES	LTG	REC	MISC	DESCRIPTION	LOAD	L1	L2	L3	LOAD	DESCRIPTION	MISC	REC	LTG	POLES	AMPS	NO.	
CL	1	20	1				EXIST ING LOAD	600	4706			4106	PANEL RH1				3	60	2	CL
CL	3	20	1				EXIST ING LOAD	600		3506		2906							4	CL
CL	5	20	1				EXIST ING LOAD	600			3506	2906							6	CL
	7	20	1				SPARE		0				SPARE				1	20	8	
CL	9	20	1				EXIST ING LOAD	600		1200		600	EXIST ING LOAD				1	40	10	
	11	20	1				SPARE	600			2600	2000	EXIST ING LOAD				1	20	12	CL
	13						SPACE		0				SPACE						14	
	15						SPACE			0			SPACE						16	
	17						SPACE				0		SPACE						18	
	19						SPACE		0				SPACE						20	
	21						SPACE			0			SPACE						22	
	23						SPACE				0		SPACE						24	
							PHASE T OT ALS (V	,	4706	4706	6106	NOTE/	S:							
							PHASE BALANCE	9%	30%	30%	39%		CIRCUIT BREAKERS SHALL BE 80% RATED							
							TOTAL CONNECTED LOAD (V	· · · ·		15518			DENOTES CONTINUOUS LOAD - DENOTES LARGEST MOTOR LOAD							
			25	% OF	- LO	NG	CONTINUOUS LOAD (LCL) AND LARGEST M			3730										
	TOTAL LOAD (WATTS)								19248		-								ĺ	
							TOTAL LOAD	(AMPS)		46.3										1

_	Short Circuit and A	rc Flash Ca	Iculation Arc-In-Box	energy = cal/cm ² at specified working distance
	I _{sc} at beginning of circuit (Amps):	30,000	PANEL RH	
m	Conductors per phase:	1		Enter working distance (inches): 18
Branch Circuit	(S)ingle conductors or (C)able:	S		Arc-In-Box Incident Energy: 22.10
nch	AL or CU:	CU		Flash Protection Boundary: 111
C	Conductor length:	552		
2	Conductor AWG or kcmil:	4/0	I _{sc} at fault (Amps) = 3,236	
H.	Metallic conduit? (Y or N):	Ν		-
	Fault Clearing Time (seconds):	2	@ 1,970 arc fault current (Amp	s)
	I _{sc} at beginning of circuit (Amps):	3,236	PANEL RH1	
m	Conductors per phase:	1		Enter working distance (inches): 18
ra	(S)ingle conductors or (C)able:	S		Arc-In-Box Incident Energy: 9.57
n ch	AL or CU:	CU		Flash Protection Boundary: 66
C	Conductor length:	237		
Branch Circuit	Conductor AWG or kcmil:	3	l _{sc} at fault (Amps) = 1,389	
Ħ	Metallic conduit? (Y or N):	Ν		-
	Fault Clearing Time (seconds):	2	@ 1,088 arc fault current (Amp	vs)

Table 130.4(D)(a) Approach Boundaries to Energized Electrical Conductors or Circuit Parts for Shock Protection for Alternating-Current Systems (All dimensions are distance from energized electrical conductor or circuit part to employee.)

(1)	(2)	(3)	(4)
	Limited Appro	oach Boundary ^b	Restricted Approach
Nominal System Voltage Range, Phase to Phase ^a	Exposed Movable Conductor ^c	Exposed Fixed Circuit Part	 Boundary^b; Includes Inadvertent Movement Adder
<50 V	Not specified	Not specified	Not specified
50 V-150 V ^d	3.0 m (10 ft 0 in.)	1.0 m (3 ft 6 in.)	Avoid contact
151 V–750 V	3.0 m (10 ft 0 in.)	1.0 m (3 ft 6 in.)	0.3 m (1 ft 0 in.)
Table 130.4(D)(b) Approa	ch Boundaries to Ene	rgized Electrical Cond	
Table 130.4(D)(b) Approa for Shock Protection, Dire (1)	ch Boundaries to Ene	rgized Electrical Cond	
Table 130.4(D)(b) Approa for Shock Protection, Dire	ch Boundaries to Ener ect-Current Voltage Sy (2)	rgized Electrical Cond stems	(4) Restricted Approact
Table 130.4(D)(b) Approa for Shock Protection, Dire	ch Boundaries to Ener ect-Current Voltage Sy (2)	rgized Electrical Cond estems (3)	luctors or Circuit Parts (4)
Table 130.4(D)(b) Approa for Shock Protection, Dire (1) Nominal Potential	ch Boundaries to Ener ect-Current Voltage Sy (2) Limited App Exposed Movable	rgized Electrical Cond estems (3) roach Boundary Exposed Fixed	(4) (4) Restricted Approac Boundary; Includes Inadvertent
Table 130.4(D)(b) Approa for Shock Protection, Dire (1) Nominal Potential Difference	ch Boundaries to Ener ect-Current Voltage Sy (2) Limited App Exposed Movable Conductor*	rgized Electrical Cond estems (3) roach Boundary Exposed Fixed Circuit Part	(4) (4) Restricted Approac Boundary; Include Inadvertent Movement Adder

SAMPLE WARNING SIGN. USE THE ACTUAL CALCULATED BY PROFESSIONAL ENGINEER.



Арр	propriate PPE Required
.10	Cal/cm2 at 18 inches

9 ft 7 in Flash Hazard Boundary 208 VAC Nominal System Voltage 42 in Limited Approach Boundary 0 in **Restricted Approach Boundary** x Trip Time @ 2 sec.

Bus:	Prot.: Max
Equipme	nt Name:



San Fernando Regional Park Infiltration Project

SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

FIRST STREET DIVERSION SINGLE LINE DIAGRAM, LOAD SUMMARY AND SCHEDULES

DWG No.

E-02

SHEET NO

25

OF


46


PLAN KEY NOTES:

- (1) (N) CONTROL PANEL
- 2 FLOW METER AND VAULT
- (3) GATE VALVE AND VAULT
- 4 PRETREATMENT UNIT
- 5 DROP MANHOLE AND DIVERSION STRUCTURE (REMOVE EXISTING MANHOLE STRUCTURE)
- (6) DROP MANHOLE AND DIVERSION STRUCTURE
- (7) 36" DIAMETER MH ACCESS SHAFT.
- 8 CONDUIT FROM CONTROL PANEL
- 9 LB CONNECTOR. SIZE AS REQUIRED.
- (10) ELECTRIC ACTUATOR

- 11 ROCKHOUSE
- (12) ROCKHOUSE (N) PANEL RH1.
- (13) RECREATION BUILDING MAIN SWITCHBOARD. UTILIZE AVAILABLE SPACE.
- (14) (N) 30' RADIO MAST CONCRETE LIGHT POLE
- (15) ELECTRICAL ROOM
- (16) RECREATION BUILDING
- (17) (N) GROUND ROD

8 A. A. A. A. TYP. 1-ø3" CORE HOLE FOR-/ ELECTRICAL CONDUIT (ZSO)(ZSC) 101(101) _____P01 <u>(C01</u> Ø36" PIPE NOTICE TO CONTRACTOR: GATE VALVE & VAULT IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CALL THE USA UNDERGROUND ALERT FOR LOCATION OF EXISTING UNDERGROUND UTILITIES NO LESS THAN TWO DAYS NOR MORE THAN SEVEN DAYS PRIOR TO CONSTRUCTION. 3 SCALE: NONE THE CONTRACTOR SHALL ASSUME SOLE RESPONSIBILITY FOR ANY DAMAGE DONE TO EXISTING UTILITIES OR STREET IMPROVEMENTS INCLUDING CONCRETE/LANDSCAPING DURING CONSTRUCTION. PREPARED BY: REVISIONS UNDERGROUND SERVICE ALERT REV. DATE BY DESCRIPTION APP'V'D CALL: TOLL FREE 811 TWO WORKING DAYS BEFORE YOU DIG






		COMPONENT SCHEDULE	
L TAG NAME	NET REQD.	DESCRIPTION	MANUFACTURER PART NO.
СВА		10A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU110
CBA		15A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU115
CBD		1A MINIATURE CIRCUIT BREAKER	SQUARE "D" - M9F21101
CBD		2A MINIATURE CIRCUIT BREAKER	SQUARE "D" - M9F21102
CBD		10A MINIATURE CIRCUIT BREAKER	SQUARE "D" - M9F21110
Y-1A	1	24VDC POWER SUPPLY (10A)	SOLA SDN 4-24 100C
Y-UPS	1	24VDC UPS (10A)	SOLA SDU 10-24
Y-BAT	1	24VDC BATTERY MODULE	SOLA SDU 24-BAT
НМІ	1	7" TOUCHSCREEN HMI + PLC	MAPLE SYSTEMS INC. HMC3070A-M
		I/O MODULE	MAPLE SYSTEMS INC. HMC3-M1212Y0200
-STAT	1	THERMOSTAT	HOFFMAN THERM16F
D LAMP	1	LED LIGHT FIXTURE AND LIGHT DOOR SWITCH WITH MOUNTING ACCESSORIES	PHOENIX 2702223 / 2702336
		INTRUSION SWITCH	HONEYWELL 13AC1
	1	RECEPTACLE DUPLEX – ISOLATED GROUND	WEIDMULLER 6720005421
HTR	1	SPACE ELECTRIC HEATER	HOFFMAN DAH2001A
AUST FAN	1	FAN & FILTER	375 CFM, PFA6000 PART NO. PTF8000 HAMMOND
_	1	ETHERNET SWITCH	RED LION N-TRON 105TX
RADIO	1	ETHERNET DATA RADIO	SCHNEIDER J-SERIES TRIO JR900
		ANALOG SURGE PROTECTORS	PHOENIX 2856126/2856023
		ISOLATED GROUND BAR	
		FLOW LOGGER	HACH FL1500
		DIN RAIL END STOP	IDEC BNL5
		FEED THROUGH TERMINAL BLOCKS M4/6 GREY	ENTRELEC 115.116
CR		CONTROL RELAY SOCKET AND PLUG-IN RELAY	SQUARE D 8501K
WD		WIRE DUCT - PANDUCT TYPE G 2.25 W X 3.12 H (TYP. ALL)	PANDUIT G2X3LG6
CBA		20A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU120
CBA		20A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU220
		PANEL "RH1", 60A, 120/240V, 1PH, 3W 12-CIRCUIT BREAKER INTERIOR. BOLT-ON BREAKERS.	
		NEUTRAL BAR	
		DIN RAIL	


DWG No. San Fernando Regional Park Infiltration Project E-04 SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD SHEET NO FIRST STREET DIVERSION CONTROL PANEL ELEVATION AND COMPONENT SCHEDULE

27

OF

46







- 1. ALL PIPING AND INSTRUMENTATION DIAGRAM SHOWS ONLY THE FUNCTIONAL SYSTEM. REFER TO MECHANICAL PLAN FOR COMPLETE PIPING DETAILS, REFER TO CONTROL SCHEMATIC DIAGRAM AND PLC WIRING FOR COMPLETE LOGIC CONTROL SEQUENCE.
- 2. RTU DESIGN, SCADA HMI AND PLC PROGRAMMING SHALL BE DONE BY BYRD ELECTRONICS.



)	CONSULT 15 Flagstone, P:(949) 317-4	700	Canyon, CA 92679 F:(206) 203-1316 www.linkture.com	Ma Di R.C.E
	DRAWN BY:	JA	APRIL 2021	
	DESIGNED BY:	JA	APRIL 2021	2
	CHECKED BY:	OF	APRIL 2021	Mar

Molon	(
Matthew Baumgardner DATE Director of Public Works Date	
E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
pappi	
anuel Fabian, Civil Engineer Assistant II DATE	




CITY OF SAN FERNANDO DEPARTMENT OF PUBLIC WORKS

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

PIPING & INSTRUMENTATION DIAGRAM

DWG No. E-05 SHEET NO 28 OF 46





	_
<u> </u>	

ELECTRICAL DESIGN LOAD SUMMARY			
SERVICE DESCRIPTION	LOAD (A)		
PANEL "A"	16.3		
SAFETY FACTOR (25% OF TOTAL LOAD)	4.1		
TOTAL AMPERE	20.4		

DWG No. San Fernando Regional Park Infiltration Project E-06 SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD SHEET NO GLENOAKS BLVD. DIVERSION SINGLE 29 LINE DIAGRAM, LOAD SUMMARY AND OF PANEL SCHEDULE 46


	(U01)			
WW			W	W
			JESSIE STREET	
		— W — — W — — — — — — — — — — — — — — —		- G W
—————————————————————————————————————	б (ОН) (ОН)	— — (OH)— — — (OH)— — 	(OH)	
NOTICE TO CONTRACTOR:			SCALE: 1" = 8'	AL PLAN
T SHALL BE THE SOLE RESPONSIBILITY OF CALL THE USA UNDERGROUND ALERT FOR L JNDERGROUND UTILITIES NO LESS THAN TY THAN SEVEN DAYS PRIOR TO CONSTRUCTION B11				
THE CONTRACTOR SHALL ASSUME SOLE RES DAMAGE DONE TO EXISTING UTILITIES OR STI NCLUDING CONCRETE/LANDSCAPING DURING UNDERGROUND SERVICE ALERT		REVISIONS		PREPARED BY:
CALL: TOLL FREE 811	REV. DATE BY	DESCRIPTION		
TWO WORKING DAYS BEFORE YOU DIG				





ELECTRICAL PLAN KEY NOTES:


- (18) GATE VALVE AND VAULT
- (19) FLOW METER AND VAULT
- (20) PRETREATMENT UNIT
- (21) CONDUIT GOING TO CONTROL PANEL
- (22) LB CONNECTOR. SIZE AS REQUIRED.
- (23) ELECTRIC ACTUATOR
- (24) EXISTING SCE PULL BOX
- (25) (N) 30' RADIO MAST CONCRETE LIGHT POLE
- (26) (N) METER PEDESTAL.
- (27) (N) GROUND ROD




TAG NAME	NET REQD.	DESCRIPTION	MANUFACTURER PART NO.
BA		10A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU110
BA		15A MINIATURE CIRCUIT BREAKER	SQUARE "D" – QOU115
3D		1A MINIATURE CIRCUIT BREAKER	SQUARE "D" - M9F21101
3D		2A MINIATURE CIRCUIT BREAKER	SQUARE "D" – M9F21102
3D		10A MINIATURE CIRCUIT BREAKER	SQUARE "D" - M9F21110
-1A	1	24VDC POWER SUPPLY (10A)	SOLA SDN 4-24 100C
UPS	1	24VDC UPS (10A)	SOLA SDU 10-24
BAT	1	24VDC BATTERY MODULE	SOLA SDU 24-BAT
MI	1	7" TOUCHSCREEN HMI + PLC	MAPLE SYSTEMS INC. HMC3070A-M
		I/O MODULE	MAPLE SYSTEMS INC. HMC3-M1212Y0200
STAT	1	THERMOSTAT	HOFFMAN THERM16F
LAMP	1	LED LIGHT FIXTURE AND LIGHT DOOR SWITCH WITH MOUNTING ACCESSORIES	PHOENIX 2702223 / 2702336
		INTRUSION SWITCH	HONEYWELL 13AC1
	1	RECEPTACLE DUPLEX – ISOLATED GROUND	WEIDMULLER 6720005421
TR	1	SPACE ELECTRIC HEATER	HOFFMAN DAH2001A
ST FAN	1	FAN & FILTER	375 CFM, PFA6000 PART NO. PTF8000 HAMMOND
	1	ETHERNET SWITCH	RED LION N-TRON 105TX
DIO	1	ETHERNET DATA RADIO	SCHNEIDER J-SERIES TRIO JR900
		ANALOG SURGE PROTECTORS	PHOENIX 2856126/2856023
		ISOLATED GROUND BAR	
		FLOW LOGGER	HACH FL1500
		DIN RAIL END STOP	IDEC BNL5
В		FEED THROUGH TERMINAL BLOCKS M4/6 GREY	ENTRELEC 115.116
R		CONTROL RELAY SOCKET AND PLUG-IN RELAY	SQUARE D 8501K
/D		WIRE DUCT – PANDUCT TYPE G 2.25 W X 3.12 H (TYP. ALL)	PANDUIT G2X3LG6
		100A, 4 JAW METER SOCKET	
		TEST BLOCKS WITH SEALABLE COVER	
		PANEL "A", 100A, 120/240V, 1PH, 3W 12–CIRCUIT BREAKER INTERIOR. BOLT–ON BREAKERS.	
		NEUTRAL BAR	
		DIN RAIL	


San Fernando Regional Park Infiltration Project E-08 SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD SHEET NO **GLENOAKS BLVD. DIVERSION** 31 METER PEDESTAL ELEVATION AND OF COMPONENT SCHEDULE


DWG No. 46



						/
		СО	NDUIT SCHEDULE]
	PLAN CONDUIT	WIRE		1000	TION	
	SYMBOL	WIRE			TION	_
CBD1 EY-UPS+ EY-UPS-	(##) QTY SIZE (")	% FILL QTY SIZE	USE	FROM	ТО	-
CBD1 EI-OFS+ EI-OFS- OA, 1P		- 3/8 NYLON ROPE	SECONDARY SERVICE	(E) SCE PULL BOX	(N) METER PEDESTAL	-
i i i i i i i i i i i i i i i i i i i	PO1 1 1 (P02) 1 1	21.28 3#8 + 1#8 GND. 5.80 2#12 + 1#12	ELECTRIC ACTUATOR	VAULT	PANEL "RH1"	-
CBD2	(P02) 1 1 (P03) 1 1	5.80 2#12 + 1#12 5.80 2#12 + 1#12	ELECTRIC ACTUATOR AS SHOWN	VAULT CONTROL PANEL	PANEL "A" PANEL "RH1"	-
	(P04) 1 1	5.80 2#12 + 1#12 5.80 2#12 + 1#12	AS SHOWN AS SHOWN	CONTROL PANEL	PANEL RHT	-
TB-DC)	(<u>P05</u>) 1 3	19.06 3#250-KCMIL + 1#8	FEEDER	RECREATION BLDG. "MSB"	PANEL "RH"	-
CBD3 A. 1P	(<u>P06</u>) 1 2	8.04 3#3 + 1#8	FEEDER	PANEL "RH"	PANEL "RH1"	-
A, 1P D-1B ETHERNET SWITCH TB-DC)	CO1 1 1	5.64 4#14	ZCO-1/ZSC-1 DISCRETE SIGNAL	VAULT	CONTROL PANEL	-
	<u>(C02)</u> 1 1 1/2	14.69 (2) MFR'S CABLE	FLOW-DAR SENSOR W/ SURCHARGE VELOCITY SENSOR	VAULT	CONTROL PANEL	-
	<u>(C03)</u> 1 1	13.20 2/C#16 TSP	LIT-1 4-20mA SIGNAL	VAULT	CONTROL PANEL	-
i i i i i i i i i i i i i i i i i i i	(<u>C04</u>) 1 1	5.64 4#14	ZCO-2/ZSC-2 DISCRETE SIGNAL	VAULT	CONTROL PANEL	
CBD5	<u>(C05)</u> 1 1 1/2	14.69 (2) MFR'S CABLE	FLOW-DAR SENSOR W/ SURCHARGE VELOCITY SENSOR	VAULT	CONTROL PANEL	
A, 1P D-1D FLOW LOGGER TA	<u>(C06)</u> 1 2	4.48 COAXIAL CABLE	ANTENNA CABLE	CONTROL PANEL	10dB YAGI ANTENNA	
TB-DC)						
R SWITCH INNER PANEL LED D-1E LIGHT W/DOOR SWITCH C			MAPLE SYSTEMS			
			HMC3-M1212Y0200			
		EY−UPS (−) ► EY−UPS (+) ►				
L EY-UPS (-)			⊠ V1	FROM BASE		
		□□				
		XXX 24N SHD				
			⊠ V2 24V (+) ⊠			
TROL TERMINAL LOCATED IN PLC/SCADA CONTROL PANEL SECTION	(*) TANK LEVEL $\begin{pmatrix} LIT + 7\\ 101 - 4 \end{pmatrix}$		1 1 1 1 1 1 1 1 1 1			
		-				
NTROL SCHEMATIC DIAGRAM	BATTERY STATUS OK			•	SPARE	
	AC POWER OK	SPR	Z X1 Y1 IS		SPARE	
		NS-101			STARE	
	INTRUSION SWITCH CONTROL PANEL		Z X2 OV IS		DO	
	(**) INTRUSION SWITCH PANEL	NS-102 ••••••••••••••••••••••••••••••••••••	12 X3 Y2 12		XXX SPARE	
	SPARE	[XXX]	Z X4 Y3 🛛			
	SPARE				XXX J SPARE	
YSTEMS INC. + PLC	SPARE	[XXX]	Z X6 Y5 🛛		Image: CR4 Image: XXX Image: CR4 Image: CR4 Image: CR4	
+ PLC ELECTRIC ACTUATOR RADIO	SPARE	[XXX]	Z X7 СОМ1 Б			
ETHERNET MODBUS TCP/IP						
	SPARE	[XXX]	Z X8 Y6 🖸			
	SPARE	[XXX]	Z X9 Y7 🛛	Ö	XXX SPARE	
	SPARE	[[XXX]	Z X10 Y8 IS			
					$\frac{1}{1000} \frac{1}{1000} \frac{1}{1000$	
	SPARE	[XXX]	Z X11 Y9 ⊠		KR8 KXX SPARE	
			Z COM COM2 ⊠			
ETHERNET SWITCH	LEGEND: (*)APPLICABLE_ONLY_FOR_F		Y10 🛛		R9 SPARE	
	(**) APPLICABLE ONLY FOR G	LENOAKS BOULEVARD				
) PLC COMMUNICATION DIAGRAM	TYPICAL I/O WIF		2 Y11 ©		R10 XXX SPARE	
	SCALE: NONE					
NE	JUALE, NUNL					
PROFESSIONA	Millen		San Fernando F	Regional Park Inf	Itration Project	DWG N E-09
1561 E. ORANGETHORPE AVE.	Matthew Baumgardner DATE Director of Public Works	SAN FERNA		PARK AND FROM FIRST STREET		SHEET
	.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	HISTORIC & VISION		CONTROL SCH		32
DRAWN BY: JA APRIL 2021	pappi	CITY OF SAN FER		& CONDUIT SC		OF
	Manuel Fabian, Civil Engineer Assistant II DATE	DEPARTMENT OF PUBLIC				46







San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

PIPING & INSTRUMENTATION DIAGRAM

DWG No. E-II SHEET NO 46

34

OF

EROSION AND SEDIMENT CONTROL NOTES:

SEDIMENTS FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON-SITE USING AN EFFECTIVE COMBINATION OF EROSION AND SEDIMENT CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE, AND STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING, OR WIND.

WASTE AND MATERIALS MANAGEMENT CONTROL NOTES:

APPROPRIATE BEST MANAGEMENT PRACTICES (BMPS) FOR CONSTRUCTION-RELATED MATERIALS, WASTES, SPILLS, OR RESIDUES SHALL BE IMPLEMENTED AND RETAINED ON-SITE TO MINIMIZE TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJOINING PROPERTY BY WIND OR RUNOFF.

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) NOTES:

IN THE CASE OF EMERGENCY, CALL:

- AT PHONE (818) 898-1243 (MANUEL FABIAN)
- 1. SEDIMENT FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON-SITE USING STRUCTURAL CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE.
- 2. STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING, OR WIND.
- 3. APPROPRIATE BMPS FOR CONSTRUCTION-RELATED MATERIALS, WASTES, SPILLS, OR RESIDUES SHALL BE IMPLEMENTED TO MINIMIZE TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJOINING PROPERTIES BY WIND OR RUNOFF.
- 4. RUNOFF FROM EQUIPMENT AND VEHICLE WASHING SHALL BE CONTAINED AT CONSTRUCTION SITES, UNLESS TREATED, TO REDUCE OR REMOVE SEDIMENT AND OTHER POLLUTANTS.
- 5. ALL CONSTRUCTION CONTRACTOR AND SUBCONTRACTOR PERSONNEL ARE TO BE MADE AWARE OF THE REQUIRED BEST MANAGEMENT PRACTICES AND GOOD HOUSEKEEPING MEASURES FOR THE PROJECT SITE AND ANY ASSOCIATED CONSTRUCTION STAGING AREAS.
- 6. AT THE END OF EACH DAY OF CONSTRUCTION ACTIVITY ALL CONSTRUCTION DEBRIS AND WASTE MATERIALS SHALL BE COLLECTED AND PROPERLY DISPOSED IN TRASH OR RECYCLE BINS.
- 7. CONSTRUCTION SITES SHALL BE MAINTAINED IN SUCH A CONDITION THAT AN ANTICIPATED STORM DOES NOT CARRY WASTES OR POLLUTANTS OFF THE SITE. DISCHARGES OF MATERIAL OTHER THAN STORMWATER ONLY WHEN NECESSARY FOR PERFORMANCE AND COMPLETION OF CONSTRUCTION PRACTICES AND WHERE THEY DO NOT: CAUSE OR CONTRIBUTE TO A VIOLATION OF ANY WATER QUALITY STANDARD; CAUSE OR THREATEN TO CAUSE POLLUTION, CONTAMINATION, OR NUISANCE; OR CONTAIN A HAZARDOUS SUBSTANCE IN A QUANTITY REPORTABLE UNDER FEDERAL REGULATIONS 40 CFR PARTS 117 AND 302.
- 8. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SOLID OR LIQUID CHEMICAL SPILLS; WASTES FROM PAINTS, STAINS, SEALANTS, GLUES, LIMES, PESTICIDES, HERBICIDES, WOOD PRESERVATIVES, AND SOLVENTS; ASBESTOS FIBERS, PAINT FLAKES, OR STUCCO FRAGMENTS; FUELS, OILS, LUBRICANTS, AND HYDRAULIC, RADIATOR OR BATTERY FLUIDS; FERTILIZERS, VEHICLE/EQUIPMENT WASH WATER, AND CONCRETE WASH WATER; CONCRETE, DETERGENT. OR FLOATABLE WASTES: WASTES FROM ANY ENGINE/EQUIPMENT STEAM CLEANING OR CHEMICAL DEGREASING AND SUPERCHLORINATED POTABLE WATER LINE FLUSHING.

DURING CONSTRUCTION, PERMITTEE SHALL DISPOSE OF SUCH MATERIALS IN A SPECIFIED AND CONTROLLED TEMPORARY AREA ON-SITE. PHYSICALLY SEPARATED FROM POTENTIAL STORMWATER RUNOFF, WITH ULTIMATE DISPOSAL IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS.

- 9. DEWATERING OF CONTAMINATED GROUNDWATER, OR DISCHARGING CONTAMINATED SOILS VIA SURFACE EROSION IS PROHIBITED. DEWATERING OF NON-CONTAMINATED GROUNDWATER REQUIRES A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT FROM THE RESPECTIVE STATE REGIONAL WATER QUALITY CONTROL BOARD.
- 10. GRADED AREAS ON THE PERMITTED AREA PERIMETER MUST DRAIN AWAY FROM THE FACE OF SLOPES AT THE CONCLUSION OF EACH WORKING DAY. DRAINAGE IS TO BE DIRECTED TOWARD DESILTING FACILITIES.
- 11. THE PERMITTEE AND CONTRACTOR SHALL BE RESPONSIBLE AND SHALL TAKE NECESSARY PRECAUTIONS TO PREVENT PUBLIC TRESPASS ONTO AREAS WHERE IMPOUNDED WATER CREATES A HAZARDOUS CONDITION.
- 12. THE PERMITTEE AND CONTRACTOR SHALL INSPECT THE EROSION CONTROL WORK AND ENSURE THAT THE WORK IS IN ACCORDANCE WITH THE APPROVED PLANS.
- 13. THE PERMITTEE SHALL NOTIFY ALL GENERAL CONTRACTORS, SUBCONTRACTORS, MATERIAL SUPPLIERS, LESSEES, AND PROPERTY OWNERS: THAT DUMPING OF CHEMICALS INTO THE STORM DRAIN SYSTEM OR THE WATERSHED IS PROHIBITED.
- 14. EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON. NECESSARY MATERIALS SHALL BE AVAILABLE ON-SITE AND STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF TEMPORARY DEVICES WHEN RAIN IS IMMINENT.
- 15. ALL REMOVABLE EROSION PROTECTIVE DEVICES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE 5-DAY RAIN PROBABILITY FORECAST EXCEEDS 40%.
- 16. SEDIMENTS FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON-SITE USING AN EFFECTIVE COMBINATION OF EROSION AND SEDIMENT CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE, AND STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, DRAINAGE FACILITIES, OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING, OR WIND.

AS THE PROJECT OWNER OR AUTHORIZED AGENT OF THE OWNER, I HAVE READ AND

UNDERSTAND THE REQUIREMENT TO CONTROL STORM WATER POLLUTION FROM SEDIMENTS, EROSION, AND CONSTRUCTION MATERIALS, AND I CERTIFY THAT I WILL COMPLY WITH THESE REQUIREMENTS, I, OR MY REPRESENTATIVE, CONTRACTOR, DEVELOPER, OR ENGINEER WILL MAKE CERTAIN THAT ALL BMPs SHOWN ON THIS PLAN WILL BE FULLY IMPLEMENTED, AND ALL EROSION CONTROL DEVICES WILL BE KEPT CLEAN AND FUNCTIONING. PERIODIC INSPECTION OF THE BMPs WILL BE CONDUCTED AND A CURRENT LOG, SPECIFYING THE EXACT NATURE OF THE INSPECTION AND ANY REMEDIAL MEASURES, WILL BE KEPT AT THE CONSTRUCTION SITE AT ALL TIMES AND WILL BE AVAILABLE FOR THE REVIEW BY THE APPROPRIATE OFFICIAL(S).

AS THE PROJECT OWNER OR AUTHORIZED AGENT OF OWNER, "I CERTIFY THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASE ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE INFORMATION SUBMITTED IS TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT SUBMITTING FALSE AND/OR INACCURATE INFORMATION, FAILING TO UPDATE THE SWPPP TO REFLECT CURRENT CONDITIONS. OR FAILING TO PROPERLY AND/OR ADEQUATELY IMPLEMENT THE EROSION CONTROL PLAN MAY RESULT IN REVOCATION OF GRADING AND/OR OTHER PERMITS OR OTHER SANCTION PROVIDED BY LAW."

PROJECT MANAGER: _____ DATE: _____

STORM WATER POLLUTION PLAN NOTES:

- FROM THE PROJECT SITE AT ALL TIMES.
- COURSES, OR WIND.
- FROM BEING TRANSPORTED FROM THE SITE BY THE FORCES OF WIND OR WATER.
- NOT BE WASHED INTO THE DRAINAGE SYSTEM.
- UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE

- AS TO INHIBIT EROSION BY WIND AND WATER.

I WILL COMPLY WITH THESE REQUIREMENTS.

SIGNATURE: _____ DATE:_____

PRINT NAME:

SEDIMENT CONTROL PLAN. FOR REVISIONS CONTACT THE PROJECT QSD. QSD: CHRIS PENDROY CERT # 24503. PHONE # (714) 526-7500 X 209.

THE FOLLOWING BMPs FROM THE LATEST ADDITION OF THE CASQA CONSTRUCTION BMP HANDBOOK (NOVEMBER 2009) MUST BE IMPLEMENTED AS APPLICABLE FOR ALL CONSTRUCTION ACTIVITIES. ADDITIONAL INFORMATION IS AVAILABLE AT WWW.CABMPHANDBOOKS.COM

EROSION CONTROL:

- EC-1 SCHEDULING EC-2 PRESERVATION OF EXISTING
- EC-3 HYDRAULIC MULCH
- EC-4 HYDROSEEDING
- EC-5 SOIL BINDERS
- EC-6 STRAW MULCH EC-7 GEOTEXTILES & MATS
- EC-8 WOOD MULCHING
- EC-9 EARTH DIKES AND DRAINAGE EC-10 VELOCITY DISSIPATION DEVIC
- EC-11 SLOPE DRAINS
- EC-12 STREAMBANK STABILIZATION EC-14 COMPOST BLANKETS
- EC-15 SOIL PREPERATION/ROUGHE EC-16 NON-VEGETATIVE STABILIZATI

TEMPORARY SEDIMENT CO

SE-1	SILT FENCE	
SE-2	SEDIMENT BASIN	
SE-3	SEDIMENT TRAP	
SE-4	CHECK DAM	
SE-5	FIBER ROLLS	
SE-6	GRAVEL BAG BERM	
SE-7	STREET SWEEPING AND VACUUM	NING
SE-8	SANDBAG BARRIER	
SE-9	STRAW BALE BARRIER	
SE-10	STORM DRAIN INLET PROTECTI	ON
SE-12	TEMPORARY SILT DIKE	
SE-13	COMPOST SOCKS AND BERMS	
SF-14	BIOFILTER BAGS	
	2.0.12.2.1 2.100	

WIND EROSION CONTROL

12

WE-1 WIND EROSION CONTROL

UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED	BY:
BEFORE	REV.	DATE	BY	DESCRIPTION AP	P'V'D	
CALL: TOLL FREE						
811						
TWO WORKING DAYS BEFORE YOU DIG						
TWO WORKING DATS BEFORE TOO DIG						

1. EVERY EFFORT SHOULD BE MADE TO ELIMINATE THE DISCHARGE OF NON-STORM WATER 2. ERODED SEDIMENTS AND OTHER POLLUTANTS MUST BE RETAINED ON-SITE AND MAY NOT BE

TRANSPORTED FROM THE SITE VIA SHEET FLOW, SWALES, AREA DRAINS, NATURAL DRAINAGE 3. STOCKPILES OF EARTH AND OTHER CONSTRUCTION RELATED MATERIALS MUST BE PROTECTED

4. FUELS, OILS, SOLVENTS, AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MAY

5. EXCESS OR WASTE CONCRETE MAY NOT BE WASHED INTO THE PUBLIC WAY OR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON-SITE

6. TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION OF RAINWATER AND DISPERSAL BY WIND. 7. SEDIMENTS AND OTHER MATERIALS MAY NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONSTRUCTION ENTRANCE ROADWAYS MUST BE STABILIZED SO AS TO INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC WAY. ACCIDENTAL DEPOSITIONS MUST

BE SWEPT UP IMMEDIATELY AND MAY NOT BE WASHED DOWN BY RAIN OR OTHER MEANS. 8. ANY SLOPES WITH DISTURBED SOILS OR DENUDED OF VEGETATION MUST BE STABILIZED SO 9. AS THE PROJECT OWNER OR AUTHORIZED AGENT OF THE OWNER, I HAVE READ AND

UNDERSTAND THE REQUIREMENTS LISTED ABOVE, NECESSARY TO CONTROL STORM WATER POLLUTION FROM SEDIMENTS, EROSION, AND CONSTRUCTION MATERIALS, AND I CERTIFY THAT


CHANGES TO THIS PLAN CAN ONLY BE MADE BY THE QSD WHO DEVELOPED THIS EROSION AND

CWE ADDRESS: 1561 E. ORANGETHORPE AVE., SUITE 240 FULLERTON, CA 92831

EQUIPMENT TRACKING CONTROL

VEGETATION	TC-1 STABILIZED CONSTRUCTION ENTRANCE/EXIT TC-2 STABILIZED CONSTRUCTION ROADWAY TC-3 ENTRANCE/OUTLET TIRE WASH
	NON-STORMWATER MANAGEMENT:
CES	NS-1 WATER CONSERVATION PRACTICES NS-2 DEWATERING OPERATIONS NS-3 PAVING AND GRINDING OPERATIONS NS-4 TEMPORARY STREAM CROSSING NS-5 CLEAR WATER DIVERSION NS-6 ILLICIT CONNECTION/DISCHARGE
ENING TION	NS-7 POTABLE WATER/IRRIGATION NS-8 VEHICLE AND EQUIPMENT CLEANING
<u>ONTROL:</u>	NS-5 CELAR WATER DIVERSION NS-6 ILLICIT CONNECTION/DISCHARGE NS-7 POTABLE WATER/IRRIGATION NS-8 VEHICLE AND EQUIPMENT CLEANING NS-9 VEHICLE AND EQUIPMENT FUELING NS-10 VEHICLE AND EQUIPMENT MAINTENANCE NS-12 CONCRETE CURING NS-13 CONCRETE FINISHING NS-14 MATERIAL AND EQUIPMENT USE NS-15 DEMOLITION ADJACENT TO WATER NS-16 TEMPORARY BATCH PLANTS
JUMING	WASTE MANAGEMENT & MATERIAL POLLUTION CONTROL:


WM-1 MATERIAL DELIVERY AND STORAGE WM-2 MATERIAL USE WM-3 STOCKPILE MANAGEMENT WM-4 SPILL PREVENTION AND CONTROL WM-5 SOLID WASTE MANAGEMENT WM-6 HAZARDOUS WASTE MANAGEMENT WM-7 CONTAMINATION SOIL MANAGEMENT WM-8 CONCRETE WASTE MANAGEMENT WM-9 SANITARY/SEPTIC WASTE MANAGEMENT WM-10 LIQUID WASTE MANAGEMENT



EROSION CONTROL SYMBOLS:


INLET PROTECTION	Ó
DIRECTION OF FLOW	_

PROJECT LIMIT



EROSION CONTROL NOTES:

30
(31) — INSTALL STORM DRAIN INLET PROTECTION (BMP SE
(32) CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE/EXIT CONTRACTOR TO DETERMINE EXACT LOCATION
(33)



MATERIAL STORAGE:

- 1. DIRT AND OTHER CONSTRUCTION RELATED MATERIALS PLACED IN THE STREET OR ON OTHER IMPERVIOUS SURFACES MUST BE CONTAINED WITH SANDBAGS OR OTHER MEASURES TO PREVENT TRANSPORT TO THE STORM DRAIN SYSTEM.
- 2. ANY CONSTRUCTION MATERIAL STORED OR STOCKPILED ON-SITE SHALL BE PROTECTED FROM BEING TRANSPORTED BY THE FORCE OF WIND OR WATER

STREET MAINTENANCE:


- 1. REMOVE ALL SEDIMENT DEPOSITED ON PAVE ROADWAYS IMMEDIATELY.
- 2. SWEEP PAVED AREAS THAT RECEIVE CONSTRUCTION TRAFFIC WHENEVER SEDIMENT BECOMES VISIBLE.
- 3. PAVEMENT WASHING WITH WATER IS PROHIBITED IF IT RESULTS IN A DISCHARGE TO THE STORM DRAIN SYSTEM.


MP SE-10) 'EXIT (BMP TC-1)

San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD


EROSION CONTROL PLAN


DWG NO. EC-0I SHEET NO. 35 OF 46







VE	1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 www.cwecorp.com	PROFESSION 4 No.85752 ★ Exp. 9/30/2022 ★				Matthew Baumgardner, DATE Director of Public Works R.C.E. NO.: <u>71932</u> EXP. DATE: <u>12/31/2021</u>	
	www.cwecorp.com	CIVIL ONT	DRAWN BY:	TT	APR 2021	1alli	
		OF CALIFOR	DESIGNED BY:	КН	APR 2021	1 * 11	
			CHECKED BY:	VB	APR 2021	Manuel Fabian, Civil Engineer Assistant II DATE	









UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED BY:
BEFORE FOR	REV.	DATE	BY	DESCRIPTION APP'V'D	
CALL: TOLL FREE					
811					
					_
TWO WORKING DAYS BEFORE YOU DIG					-





1. CONTRACTOR TO VERIFY ALL DIMENSIONS IN THE FIELD 2. CONTRACTOR TO COORDINATE LOCATION OF ALL UTILITIES (CALL BEFORE YOU DIG) . ALL SIDEWALKS, CONCRETE SURFACES, PLAY SURFACES AND FENCES ARE TO REMAIN 4. PROTECT ALL EXISTING TREES IN PLACE – PLANTING PLAN DETAIL (1) 5. FOLLOW PLANTING SPECIFICATIONS FOR SHRUBS – PLANTING PLAN DETAIL (2) 6. FOLLOW PLANTING SPECIFICATIONS FOR TREES – PLANTING PLAN DETAIL (3) 7. ENTIRE AREA IS TO BE ROTOTILLED TO A DEPTH OF 8"

9. FOLLOW SPECIFICATIONS REGARDING SOIL COMPACTION AND TOPSOIL AMENDMENTS 10. FOLLOW MANUFACTURERS SPECIFICATIONS FOR DECOMPOSED GRANITE INSTALLATION 11. FOLLOW MANUFACTURERS SPECIFICATIONS FOR INFIELD MIX INSTALLATION FOR



FIRST ST

LOCATION KEY 0 50 100 200

	and the second			
SC	ALE:	1=	200	


PLANT/MATERIAL KEY							
SYMBOL	BOTANICAL NAME COMMON NAME	QUANTITY	NOTES				
v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v v	MARATHON SOD	211,939 SF	SOD OVER 5" PREFERRED				
	BASEBALL DIAMOND DIRT	13,825 SF	DIAMOND PRO OVER 50% BRICK 30% SAND AND 20% DG FINE MIX AS A BINDER @6" DEEP				
	STABILIZED DECOMPOSED GRANITE	13,481 SF	3" OF STABILIZED DG OVER COMPACTED SUBGRADE OF NATIVE SOIL				
	TREE RING DRIPLINE W/ BARK MULCH	10,956 SF	3" DEEP SHREDDED BARK MULCH BELOW ALL TREE DRIPLINES				
	RHAPIOLEPSIS INDICA INDIAN HAWTHORNE	41- 5 GAL					
	DIETES VEGETA AFRICAN IRIS	38- 1 GAL					
	BARK MULCH	2,906 SF	¹ / ₂ "-3/4" BARK MULCH @ 3" DEEP				
	QUERCAS AGRIFOLIA COAST LIVE OAK	3– 24" BOX					



DWG NO. LS-02 SHEET NO. 41 OF 46


CITY OF SAN FERNANDO DEPARTMENT OF PUBLIC WORKS

PLANTING PLAN




2. IF THERE IS NO EXISTING IRRIGATION, SEE SPECIFICATIONS FOR WATERING REQUIREMENTS.

4. NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING



SEAL: 1561 E. ORANGETHORPE AVE. SUITE 240 FULLERTON, CA 92831 TEL (714) 526-7500 10/31/19 Renewal Da 11/9/17 Date www.cwecorp.com DRAWN BY: DESIGNED BY: CHECKED BY: KM




PLANTING IRRIGATION POINT-OF-CONNECTION NOTES:

IRRIGATION LEGEND									
SYMBOL	DESCRIPTION	MANUFACTURER	PART # AND DESCRIPTION	DETAILS					
Μ	WATER METER	NA							
	BACKFLOW PREVENTER	NA							
-	P.O.C.								
BP	BOOSTER PUMP	MUNROE	COMPLETE PRO II						
\prec	Y STRAINER	WILKENS ZURN	3 YB WILKINS Y STRAINER						
MCV	MASTER CONTROL VALVE	BUCKNER	SUPERIOR 3200 3"	A/5					
	MAINLINE		PVC CLASS 315 3" PIPE						
	LATERAL LINE		SCHEDULE 40 PVC						
С	IRRIGATION CONTROLLER	WEATHERMATIC	SL4800 SOLAR CONTROLLER W/ FLOW SMARTLINK BUNDLE	Н/6					
$\mathbf{\hat{e}}$	CONTROL VALVE WITH VALVE BOX 2"	RAINBIRD	RAINBIRD 200 PEB 2" WITH PRS DIAL	B/5					
	CONTROL VALVE WITH VALVE BOX 1-1/2"	RAINBIRD	RAINBIRD 150PEB 1.5" WITH PRS DIAL	B/5					
\otimes	CONTROL VALVE WITH VALVE BOX !'	RAINBIRD	RAINBIRD 100 PEB 1" WITH PRS DIAL	B/5					
	GATE VALVE WITH VALVE BOX	RAINBIRD	GATE VALVE AWWA C-500 WITH VALVE BOX RAINBIRD VB SERIES PVBSTD 12" STANDARD	I/5					
	QUICK COUPLER WITH VALVE BOX	RAINBIRD	TRIPLE SWING ASSEMBLY BRASS 44-R VALVE BOX: VB SERIES PVBSTD 12" STANDARD	C/5					


SYMBOL	DESCRIPTION	MANUFACTURER	PART # AND DESCRIPTION	PATTERN/GPM	RADIUS	PSI
\bigcirc	TURF ROTOR	RAINBIRD	8005 SS FULL CIRCLE ROTOR NOZZLE 10	FULL CIRCLE 9.3 GPM	55'-0"	50
	TURF ROTOR	RAINBIRD	8005 SS FULL CIRCLE NOZZLE 6	FULL CIRCLE 5.6GPM	45'-0"	50
	TURF ROTOR	RAINBIRD	8005 SS HALF CIRCLE NOZZLE 10	HALF 9.3 GPM	55	50
	TURF ROTOR	RAINBIRD	5000 SERIES STD. RAINCURTAIN NOZZLE 4.0LA	ADJUSTABLE PART CIRCLE-REVERSE FULL CIRCLE 4.01 GPM	40'-35'	45
	SPRINKLER HEADS	RAINBIRD	1800 SERIES MPR 12 SERIES	H F 1.3 2.6	1'-0"	30
н	SPRINKLER HEADS	RAINBIRD	1800 SERIES MPR 8 SERIES NOZZLE	H .52GPM	5'-0"	30

THE LANDSCAPE ARCHITECT, KATHLEEN MCKERNIN AT 310-795-4886, FOR ADDITIONAL DIRECTIVE.



FIRST ST


L	.00	CA	T	ION	I K	EY
0	5	50	1	00		200
	SC	ALE	-:	1 =	20	0



San Fernando Regional Park Infiltration Project SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD

DWG No. LS-04 SHEET NO. 43 OF 46


IRRIGATION PLAN



ED. IC			

	IRRIGATION PRESSURE CALCULATION								
		VALVE E	3-2 FURTHEST S	SHRUB					
UNITS	SIZE	TYPE	DESCRIPTION	PSI LOSS	TL. UNIT PSI LOSS				
1	0'-3"	PRESS.	"Y" STRAINER	1	1				
1	0'-3"	ANGLE	MASTER VALVE	2.6000	2.6000				
1	0'-1 1/2"	BRASS	AUTOMATIC VALVE	3.6000	3.6				
4	0'-3"	BRASS	GATE VALVE	0	0				
1109.5	0'-3"	CL315	MAINLINE	4.12 @ 100'	45.7100				
5'/10'/10'	0'-0 1/2"	SCH 40 PVC	LATERAL LINE	2.11,3.36,4.22@100'	1.8000				
10'-0", 10'-0", 0'-0"	0'-0 3/4"	SCH40	LATERAL LINE	4.2,4.8@100'	0.9000				
10',10',10',10'	0'-1"	SCH 40	LATERAL LINE	3.7,4.07,4.44,2.99	1.5000				
6'	0'-1 1/4"	SCH 40	LATERAL LINE	3.42@100'	0.2050				
10'-0"	0'-2"	SCH 40	LATERAL LINE	3.77@100'	0.3770				
				SUB-TOTAL	57.7620				
			FITTINGS ALLOWANCE		5.7000				
5'-0"			ELEVATION LOSSES	0.4330	2.1650				
			MIN REQ'D BY HEAD	30	30				
			TOTAL PRESSURE REQ'D		95.5620				
			EXIST STATIC PRESSURE	90PSI	90				
			RESIDUAL PRESSURE		-5.5600				
			BOOSTER PUMP NEEDED						

IRRIGATION PRESSURE CALCULATION									
VALVE A-16 LARGEST TURF									
UNITS	SIZE	TYPE	DESCRIPTION	PSI LOSS	TL. UNIT PSI LOSS				
1	0'-3"	PRESS.	"Y" STRAINER	1	1				
1	0'-3"	ANGLE	MASTER VALVE	2.6000	2.6000				
1	0'-2"	BRASS	AUTOMATIC VALVE	4.5000	4.5000				
5	0'-3"	BRASS	GATE VALVE	0	1				
545'-0"	0'-3"	CL315	MAINLINE	4.12 @ 100'	22.4500				
56'-0"	0'-1"	SCH 40	LATERAL LINE	3.7@100'	2.0720				
50'-0"	0'-1 1/4"	SCH 40	LATERAL LINE	4.25@100'	2.1250				
81'-0"	0'-1 1/2"	SCH 40	LATERAL LINE	4.4@100'	3.5640				
108'-0"	0'-2"	SCH 40	LATERAL LINE	4.77@100'	5.1500				
				SUB-TOTAL	93.7100				
			FITTINGS ALLOWANCE		9.3700				
4'-0"			ELEVATION LOSSES	0.4330	1.7300				
			MIN REQ'D BY HEAD	50	50				
			TOTAL PRESSURE REQ'D		99.1400				
			EXISTING STATIC PRESSURE	90PSI	90				
			RESIDUAL PRESSURE		-9.9100				
			BOOSTER PUMP NEEDED						



1 10" ROUND VALVE BOX (DO NOT CUT ADDITIONAL HOLES INTO BOX) (2) FINISH GRADE (3) 8" CL 160 PVC SLEEVE (TO REST ON TOP EDGE OF VALVE ASSEMBLY) (4) ISOLATION GATE VALVE WITH 2" SQUARE OPERATING NUT (SEE SPECIFICATIONS) $(5)\frac{3}{4}$ " GRAVEL SUMP IN, UNDER, AND AROUND VALVE BOX. FILL TO TOP OF VALVE BOX HOLES

(6) INSTALL FILTER FABRIC AROUND GRAVEL SUMP (7) FLGxSLIP SCH. 80 PVC FLANGE (2 REQUIRED)

(8) PRESSURE SUPPLY LINE (REFER TO PLAN FOR SIZE)

ISOLATION GATE VALVE San Fernando Regional Park Infiltration Project

LS-05 SAN FERNANDO RECREATION PARK AND FROM FIRST STREET TO GLENOAKS BOULEVARD SHEET NO. 44

IRRIGATION DETAILS

OF

46

DWG No.

		В	ORING	LC)G	NC). B-1					F	Page 1 of	1
PR	OJECT:	San Fernando Regional Park Inf Project	iltration		CLIE	NT:	CWE Corp Fullerton, 0	oratio CA	on					
SIT	E:	208 Park Avenue San Fernando, CA												
OG	LOCATIO	N See Exhibit A-2		Ţ.	EL DNS	ΡE	E.,	STI	RENGTH		(%)	cl)	ATTERBERG LIMITS	NES
GRAPH		.2797° Longitude: -118.4342°		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	TEST TYPE	COMPRESSIVE STRENGTH (tsf)	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	LL-PL-PI	PERCENT FINES
	DEPTH POO	RLY GRADED SAND WITH SILT (SP-SM),	brown			Т			Ō					
	2.5			-	-									12
	<u>P00</u>	<u>RLY GRADED SAND (SP)</u> , brown, medium	n dense	-	-	X	9-10-15				3	104		4
				5-	-	X	12-12-13 N=25							
	very	dense		-	-		23-50/6"				4	131		
	10.0 <u>SILT</u>	Y SAND (SM), brown, very dense		- 10-	-	\bigtriangledown	26-36-30							18
				-	-	\square	N=66							
	15.0 POO	RLY GRADED SAND (SP), brown, very de	nse	- 15- -			40-50/5"				4	127		
				-	-									
				20	-	X	31-40-37 N=77							
	25.1			- - 25-	-									
		ecovery ng Terminated at 25.1 Feet	/	20			50/1"							
	Stratificati	on lines are approximate. In-situ, the transition may l	be gradual.				Hamı	mer Typ	e: Auton	hatic				
	cement Meth ow stem aug						Notes	:						
	onment Meth ng backfilled		ee Appendix C fo bbreviations.	or expla	nation c	of syn	nbols and							
	101 102	R LEVEL OBSERVATIONS					Boring	Started:	05-15-20	018	Borii	ng Com	pleted: 05-15-	2018
	Groundw	vater not encountered	lier					g: CME	75		Drill	er:		
			1421 E	dinger Tustin,	Ave, St CA	e C	Project	No.: 60	185012		Exhi	bit:	A-3	


TE	EST PIT L	.00	G N	0.	Tre	nch					F	Page 1 of	1
PROJECT: San Fernando Regional Park I Project	nfiltration		CLIE	NT:	CWE Fuller	Corpor rton, C/	ratic A	on					
SITE: 208 Park Avenue San Fernando, CA													
ဗ္မ LOCATION See Exhibit A-2		~	NS	ЫЕ	Т		STF	RENGTH	TEST	(%	. (j:	ATTERBERG LIMITS	ES I
LOCATION See Exhibit A-2 Latitude: 32.2794° Longitude: -118.4346°		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST	RESULTS	TEST TYPE	COMPRESSIVE STRENGTH (tsf)	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	LL-PL-PI	PERCENT FINES
CLAYEY SAND (SC), brown		_											
POORLY GRADED SAND WITH GRAVEL (SI	<u>P)</u> , with	- - 5 - -	-										
POORLY GRADED SAND WITH GRAVEL (SI cobbles and boulders, gray	P) , with	-											
10.0 Trench is 20 feet long in the northeast-south along the existing soccer field. The lattitude a are to the center of the trench. Test Pit Terminated at 10 Feet	west direction and longitude	10-											
Stratification lines are approximate. In-situ, the transition ma	ay be gradual.					Notes:							
Back hoe						NULUES.							
Abandonment Method: Boring backfilled with auger cuttings upon completion.	See Appendix C for abbreviations.	· explai	nation o	of syn	nbols and								
WATER LEVEL OBSERVATIONS					1.67	Test Pit S	tarted	: 05-15-2	018	Test	Pit Con	npleted: 05-15	5-2018
Groundwater not encountered	ller	٢٦		C	Π	Excavator	: CME	E 75		+	rator:		
	1421 Ec	dinger / Tustin,	Ave, St CA	e C		Project No	o.: 601	185012		Exhi	bit:	A-7	

			BORING	L	O
PR	OJECT:	San Fernando Regional Park Iı Project	nfiltration		•
SIT	E:	208 Park Avenue San Fernando, CA			
ОG	LOCATIO	Ŋ See Exhibit A-2		<u> </u>	
GRAPHIC LOG		.2793° Longitude: -118.4347°		DEPTH (Ft.)	
	DEPTH POO	RLY GRADED SAND (SP), trace gravel,	brown		
	2.5				_
		(EY SAND (SC), brown, dense			_
	5.0			5	_
	SILT	<u>Y SAND (SM)</u> , trace gravel, brown, very (dense	Э	_
					_
	dens	9			-
					-
	very	dense		10)—
					-
					-
					_
					-
				15	5-
					_
					_
					_
					_
	20.0	RLY GRADED SAND WITH CLAY (SP-S	c) brown	20)—
	very	dense	<u>c</u>] , brown,		_
					_
					_
					_
	255			25	5-
	25.5 trace Bori	gravei ng Terminated at 25.5 Feet			
	Stratificati	on lines are approximate. In-situ, the transition ma	y be gradual.		
	cement Meth ow stem aug				
	onment Mething backfilled	od: with auger cuttings upon completion.	See Appendix C fo abbreviations.	r exp	la
	WATE	R LEVEL OBSERVATIONS			
	Groundw	rater not encountered	ller	ſ	-
			1421 E	dinge	er /


	E	ORING	LO)(
PRC	JECT: San Fernando Regional Park Project	Infiltration		С
SITE	208 Park Avenue San Fernando, CA			
უ ს	OCATION See Exhibit A-2		(;	
GRAPHIC LOG	atitude: 34.2804° Longitude: -118.4352°		DEPTH (Ft.)	
	EPTH			
	POORLY GRADED SAND (SP), trace sand, tra dark brown	ce gravel,		_
7.			5	
00000	SILTY SAND WITH GRAVEL (SM), light brown	, very dense	10	_
	5.0 SILTY SAND WITH GRAVEL (SM), light brown	verv dense	15	_
			00	
20	No Recovery	/	20	
	Boring Terminated at 20.4 Feet			
	Stratification lines are approximate. In-situ, the transition may be	gradual.		
Adverses	want Mathead			
	nent Method: / stem auger	See Exhibit A-5 f cedures. See Appendix B tory procedures a	for de	sci
	ment Method: backfilled with auger cuttings upon completion.	See Appendix C and abbreviation	for ex	
	WATER LEVEL OBSERVATIONS			

Abandonment Method: Boring backfilled with auger cuttings upon completion.	See Appendix C for e and abbreviations.
WATER LEVEL OBSERVATIONS	
Groundwater not encountered	llerr
	1421 Edinge Tusti

UNDERGROUND SERVICE ALERT				REVISIONS	PREPARED BY:
CALL: TOLL FREE	REV.	DATE	BY	DESCRIPTION APP'V'D	
811					
TWO WORKING DAYS BEFORE YOU DIG					




	BORING L	.00	G N	10	. BP-	2					F	Page 1 of	1
PROJECT: San Fernando Regional Park Project	Infiltration	C	CLIE	NT	: CWE Fuller	Corpo ton, C	ratio A	on					
SITE: 208 Park Avenue San Fernando, CA													
ပ္မ LOCATION See Exhibit A-2		-	EL	ΡE	L L		STF	RENGTH	TEST	(%		ATTERBERG LIMITS	ES ES
O LOCATION See Exhibit A-2 O Latitude: 34.2818° Longitude: -118.4336° Latitude: 34.2818° Longitude: -118.4336° Latitude: 34.2818° Longitude: -118.4336°		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST	ULTS	ΥPE	COMPRESSIVE STRENGTH (isf)	(%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)		PERCENT FINES
L L L L L L L L L L L L L L L L L L L		DEPT	/ATEF 3SER	MPL	FIELD	RES	TEST TYPE	APRE: (ISf)	STRAIN (%)	NO WA	DRY VEIGI	LL-PL-PI	RCE
DEPTH			NВ	S∕	_		۳	CON	ST	0	>		H
ASPHALT, 4" thickness AGGREGATE BASE COURSE, 8" thickness		_											
SILTY SAND (SM), trace gravel, dark brown		_										NP	18
		_											
POORLY GRADED SAND WITH SILT (SP-SM gravel, very dense, no Recovery	<u>∕I)</u> , trace	5—			50/	/4"							
trace gravel, brown/black		_		X	17-5	0/5"							
		10											
		10—		X	29-5	0/5"]			2	114		
		_											
		_											
		15—											
tan/white		_		Х	21-29 N=								
Boring Terminated at 16.5 Feet													
Stratification lines are approximate. In-situ, the transition may l	be gradual.					Hamme	er Type	: Automa	tic				
Advancement Method:						Notes:							
Hollow stem auger	See Exhibit A-5 for cedures.												
Abandonmont Mathadi	See Appendix B fo tory procedures ar	nd add	itional	data	(if any).								
Abandonment Method: Boring backfilled with Auger Cuttings Surface capped with asphalt	See Appendix C for and abbreviations.		anatio	n of s	symbols								
WATER LEVEL OBSERVATIONS						Denix : Ci		0.00.001		n d			040
Groundwater not encountered	ller			Г	חו	Boring Sta			0	_		leted: 12-03-20	610
	1421 Edi	inger A	ve, Ste	_		Drill Rig: (+		ni Drilling	
	T	ustin, C	CA	-		Project No	b.: 6018	35012		Exhit	oit:	A-7	





BORING L	OG NO. BP-7 Page 1 of 1	BORIN	G LOG NO. BP-8	Page 1 of 1	BORIN	g log no. BP-8A	Page 1 of 1
ROJECT: San Fernando Regional Park Infiltration Project	CLIENT: CWE Corporation Fullerton, CA	PROJECT: San Fernando Regional Park Infiltratio Project	CLIENT: CWE Corporation Fullerton, CA		PROJECT: San Fernando Regional Park Infiltrat Project	ion CLIENT: CWE Corporation Fullerton, CA	
SITE: 208 Park Avenue San Fernando, CA		SITE: 208 Park Avenue San Fernando, CA			SITE: 208 Park Avenue San Fernando, CA		
LOCATION See Exhibit A-2 Latitude: 34.2856° Longitude: -118.4299°	MATER LEVEL WATER LEVEL OBSERVATIONS SAMPLE TYPE RESULTS RESULTS RESULTS RESULTS SAMPLE TYPE I 14-1-1-1 DRY UNIT DRY UNIT DR	Latitude: 34.2867° Longitude: -118.4285°	DEPTH (Ft) WATER LEVEL OBSERVATIONS SAMPLE TYPE RESULTS RESULTS RESULTS STRENGTH STRENGTH BIA	ATTERBERG DRY UNIT MEIGHT (%) Id HTHER DRY UNIT MEIGHT (%) Id HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER HTTHER H	LOCATION See Exhibit A-2 Latitude: 34.2867° Longitude: -118.4285°	DEPTH (Ft.) DEPTH (Ft.) DBSERVATIONS SAMPLE TYPE SAMPLE TYPE RESULTS RESULTS RESULTS RESULTS RESULTS RESULTS	ATTERRAIN (%) Identified and the state of t
DEPTH 0.2_/ <u>ASPHALT</u> , 2.5" thickness SILTY SAND (SM), trace sand, trace gravel, brown		DEPTH			DEPTH C3_A <u>ASPHALT</u> , 3" thickness SILTY SAND WITH GRAVEL (SM), brown, very dense		
5.0			5-10-30	6 120		5	
POORLY GRADED SAND (SP), trace gravel, brown, medium dense	11-11-16 	Auger Refusal at 5.3 Feet	50/4"		7.5 POORLY GRADED SAND WITH SILT (SP-SM), trace	26-50/5"	5 95
light brown, very dense	0- 6-23-27 N=50				gravel, light brown, dense very dense	10- 10- 21-50/5"	3 133
.0 SILTY SAND (SM), trace gravel, brown, very dense .3 Boring Terminated at 16.3 Feet	5-11-28-50/4" 3 129					1524-50/4"	
						20 20 20 50/21	
					Boring Terminated at 20.8 Feet	2026-50/3"	3 119
Stratification lines are approximate. In-situ, the transition may be gradual.	Hammer Type: Automatic	Stratification lines are approximate. In-situ, the transition may be gradual.	Hammer Type: Automatic		Stratification lines are approximate. In-situ, the transition may be gradual.	Hammer Type: Autom	naic
cedures.	description of field pro-	cedures.	A-5 for description of field pro-		cedures.	bit A-5 for description of field pro-	
onment Method	d additional data (if any). r explanation of symbols	Abandonment Method:	ures and additional data (if any). dix C for explanation of symbols		Abandonment Method:	edures and additional data (if any). endix C for explanation of symbols	
	Boring Started: 11-28-2018 Boring Completed: 11-28-2018 Drill Rig: CME 75 Driller: Martini Drilling Project No.: 60185012 Exhibit: A-12	Groundwater not encountered	421 Edinger Ave, Ste C	Boring Completed: 11-28-2018 Driller: Martini Drilling Exhibit: A-13	WATER LEVEL OBSERVATIONS Groundwater not encountered	Boring Started: 11-28-201 Drill Rig: CME 75 1421 Edinger Ave, Ste C Tustin, CA	18 Boring Completed: 11-28-2018 Driller: Martini Drilling Exhibit: A-14
I Iu	אווו, איז די איז איז איז איז איז איז איז איז איז אי		Tustin, CA Project No.: 60185012		L		LAIRDIL A-14
DERGROUND SERVICE ALERT		VISIONS	PREPARED BY:		0022330		
FFORE ES	REV. DATE BY		PP'V'D		AND AND L. A		

UNDERGROUND SERVICE ALERI				REVISIONS		
BEFORE FOR	REV.	DATE	BY	DESCRIPTION	APP'V'D	
CALL: TOLL FREE						
811						
TWO WORKING DAYS BEFORE YOU DIG						

PR	OJECT: San Fernando Regional Park Project	Infiltration		CLIE	NT	CWE Corpo Fullerton, C	rati A	on					
SIT	E: 208 Park Avenue San Fernando, CA												
2	LOCATION See Exhibit A-2			EL ONS	ΡE	t a	STI	RENGTH 1	EST	(%	cf)	ATTERBERG LIMITS	FINES
	Latitude: 34.2834° Longitude: -118.4309°		DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	TEST TYPE	COMPRESSIVE STRENGTH (sf)	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEGHT (pcf)	LL-PL-PI	PERCENT FII
				≥ 8	\$		۳	CON	SI	0	>		Н
	0.3 <u>ASPHALT</u> , 4" thickness POORLY GRADED SAND WITH GRAVEL (SI 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 1990 - 19900 - 1990 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900 - 19900	<u>),</u> brown	-	-									
	very dense		- 5 -	-		23-38-50/4"	-			2	120		
0			-			23-30-30/4					120		
	7.5 SILTY SAND (SM), trace gravel, brown, mediu	m dense	-	-	X	15-7-10 N=17	-						
	very dense, no recovery		10-	-	X	35-50/5"	-						
0	15.0 POORLY GRADED SAND WITH GRAVEL (Si 16.5 Boring Terminated at 16.5 Feet	2) , brown,	- - 15- -	-	X	20-25-19 N=44	-						
	Stratification lines are approximate. In-situ, the transition may b	e gradual.				Hamme	er Type	: Automa	IC				
ollo	ement Method: w stem auger nment Method: ng backfilled with Auger Cuttings	See Exhibit A-5 cedures. See Appendix E tory procedures See Appendix C	3 for des and ad C for exp	criptio ditiona	n of la I data	bora- (if any).							
Surfa	WATER LEVEL OBSERVATIONS	and abbreviatio	ns.										
			Boring Started: 12-03-2018 Boring Completed: 12-03 Drill Rig: CME 75 Driller: Martini Drilling					leted: 12-03-20	018				
	Groundwater not encountered						-	-					







E	BORING LO	OG	i NC).	BP-6					F	Page 1 of ²	1
PROJECT: San Fernando Regional Park Project	Infiltration	CI		T:	CWE Corpo Fullerton, C	ratio A	on					
SITE: 208 Park Avenue San Fernando, CA												
DEPTH	עבטברו לניל ו	WATER LEVEL	OBSERVATIONS SAMOLE TVPF		FIELD TEST RESULTS	TESI TYPE	COMPRESSIVE STRENGTH S STRENGTH S (Isf) H	STRAIN (%)	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	ATTERBERG LIMITS LL-PL-PI	PERCENT FINES
0.6 <u>ASPHALT</u> , 7" thickness <u>POORLY GRADED SAND WITH SILT (SP-SM</u> gravel, light brown 5.0 very dense		_ _ _ 5 _ _	N	<	50/2"		0					
dense	1	- - 0- - - -			20-46-37				5	122		
tan, very dense, little sample recovered Boring Terminated at 15.4 Feet		5			50/5" ,	г Туре	Automa	tic				
dvancement Method: Hollow stem auger bandonment Method: Boring backfilled with Auger Cuttings Surface capped with asphalt	See Exhibit A-5 for c cedures. See Appendix B for tory procedures and See Appendix C for and abbreviations.	descrip additio	ption of onal da	lab ta (i	ora- f any). mbols							
WATER LEVEL OBSERVATIONS Groundwater not encountered	Tierr 1421 Eding Tus		e, Ste C		Boring Sta	ME 75	5	3	-	r: Martir	leted: 11-28-20 ii Drilling A-11	118

O. BP-9 Page 1 of 2	BORING	LOG NO. BP	-9 Page 2	of 2
T: CWE Corporation Fullerton, CA	PROJECT: San Fernando Regional Park Infiltration Project	CLIENT: CWE Fulle	Corporation rton, CA	
	SITE: 208 Park Avenue San Fernando, CA			
L STRENGTH TEST	UCATION See Exhibit A-2	ST S	の STRENGTH TEST レビーンジート 会 人TTERBE LIMITS	
PERCENT FIELD TEST FIELD TEST TEST TYPE STRAIN (%) COMPRESSIVE (ssi) HIDNI WEIGHT (%) DRY UNIT WEIGHT (%) PERCENT FINES	COCATION See Exhibit A-2	DEPTH (Ft.) WATER LEVEL OBSERVATIONS SAMPLE TYPE	RESULTS RESULTS TEST TYPE COMPRESSIVE STRAIN (%) STRAIN (%) STRAIN (%) CONTENT (%) REGATH CONTENT (%) CONTENT (%	PERCENT FINES
	DEPTH POORLY GRADED SAND WITH SILT (SP-SM), trace		50/3"	PE
26	gravel, very dense <i>(continued)</i> no recovery			
12-15-15 5 129				
	35.1			
3-12-50/4"	No recovery // Boring Terminated at 35.1 Feet)/1"	
12-15-11 4 105				
17-33-36 N=69				
50 3 130				
22-50/3"				
Hammer Type: Automatic	Stratification lines are approximate. In-situ, the transition may be gradual.		Hammer Type: Automatic	
Notes:	cedures.	5 for description of field pro-	Notes:	
i labora- ta (if any). f symbols	Abandonment Method: Paring heat/filed with augus autings upon completion See Appendix O	B for description of labora- s and additional data (if any). C for explanation of symbols		
	WATER LEVEL OBSERVATIONS	ons.		20.0010
Boring Started: 11-28-2018 Boring Completed: 11-28-2018 Drill Rig: CME 75 Driller: Martini Drilling		racon	Boring Started: 11-28-2018 Boring Completed: 11-2 Drill Rig: CME 75 Driller: Martini Drilling	28-2018
Project No.: 60185012 Exhibit: A-15	1421	Edinger Ave, Ste C Tustin, CA	Project No.: 60185012 Exhibit: A-16	
XY OR	Son Eornando Dociono	Dorle In	filtration Draigat	DWG
0. '	San Fernando Regiona		_	BL-
SAN FERNANDO	SAN FERNANDO RECREATION PARK AND FR	ROM FIRST STREE	ET TO GLENOAKS BOULEVARD	SHEE
HISTORIC & VISIONARY				4
				1

BORING LOGS

OF

46