

CITY OF SAN FERNANDO
CALIFORNIA

ADDENDUM NO.2
FOR
FISCAL YEAR 2022-2023
PHASE 1, ANNUAL STREET RESURFACING PROJECT
JOB NO. 7617, PLAN NO. P-739



Prepared by:



23241 Arroyo Vista
RANCHO SANTA MARGARITA, CA 92688
(949) 888-6513

Date: 07/29/2022

ADDENDUM NO.2

- 1) All pavement cracks $\geq 1/4$ -inch wide shall be repaired.

In addition to following the product installation guidelines provided by the crack-fill manufacturers, the following crack repair procedures shall be performed:

- Remove loose particles, debris, dust, and organics from the cracks. These cracks should be brushed clean and blown with compressed hot air to remove debris, dust, and moisture. Weeds should be removed, and herbicides shall be sprayed. The cracks should be dry before applying crack fill material.
- Crack fill shall be squeegeed flush to 1/8-inch below flush.
- Cracks that settle shall be refilled to flush.

Crack seal material shall be a hot-applied, rubberized crack-fill material, such as CRAFCO Polyflex Type 3 sealant or equal.

Product Delivery, Storage, and Handling must comply with manufacturer's recommendations.

If required to complete the work, CONTRACTOR shall post "No Parking" signs and notify all residents.

Cracks repairs must be performed at least **2 weeks** prior to slurry seal.

- 2) Crack seal bid price: Pavement Crack Sealing shall be paid for at the LUMP SUM contract price with bid item 5 (and bid item 14 for the optional scope) and shall include full compensation for all labor, notification, materials, tools and equipment necessary.